



Test Report No. 608331-4-6
Test Report Date: March 2020

**MASH TL-3 EVALUATION OF 2019 MASH 2-TUBE BRIDGE
RAIL THRIE BEAM TRANSITION**

by
William F. Williams, P.E.
Associate Research Engineer
Wanda L. Menges
Research Specialist
Glenn E. Schroeder
Research Specialist
and
Darrell L. Kuhn, P.E.
Research Specialist



Contract No.: 1602767
Test No.: 608331-01-4 / 608331-01-5 / 608331-01-6
Test Date: 2019-09-02 / 2019-09-05 / 2019-12-19

Sponsored by
**State of Alaska Department of Transportation and Public
Facilities and North Dakota Department of Transportation**

TEXAS A&M TRANSPORTATION INSTITUTE PROVING GROUND

Mailing Address:
Roadside Safety & Physical Security
Texas A&M University System
3135 TAMU
College Station, TX 77843-3135

Located at:
Texas A&M University System RELLIS Campus
Building 7091
3100 State Highway 47
Bryan, TX 77807



DISCLAIMER

The contents of this report reflect the views of the authors, who are solely responsible for the facts and accuracy of the data, and the opinions, findings, and conclusions presented herein. The contents do not necessarily reflect the official views or policies of the State of Alaska Department of Transportation and Public Facilities, North Dakota Department of Transportation, The Texas A&M University System, or Texas A&M Transportation Institute. This report does not constitute a standard, specification, or regulation. In addition, the above listed agencies/ companies assume no liability for its contents or use thereof. The names of specific products or manufacturers listed herein do not imply endorsement of those products or manufacturers.

The results reported herein apply only to the article tested. The full-scale crash tests were performed according to TTI Proving Ground quality procedures and according to the *MASH* guidelines and standards.

The Proving Ground Laboratory within the Texas A&M Transportation Institute's Roadside Safety and Physical Security Division ("TTI Lab" or "TTI LAB") strives for accuracy and completeness in its crash test reports. On rare occasions, unintentional or inadvertent clerical errors, technical errors, omissions, oversights, or misunderstandings (collectively referred to as "errors") may occur and may not be identified for corrective action prior to the final report being published and issued. If, and when, the TTI Lab discovers an error in a published and issued final report, the TTI Lab shall promptly disclose such error to State of Alaska Department of Transportation and Public Facilities, North Dakota Department of Transportation, and all parties shall endeavor in good faith to resolve this situation. The TTI Lab will be responsible for correcting the error that occurred in the report, which may be in form of errata, amendment, replacement sections, or up to and including full reissuance of the report. The cost of correcting an error in the report shall be borne by TTI Lab. Any such errors or inadvertent delays that occur in connection with the performance of the related testing contract shall not constitute a breach of the testing contract.

THE TTI LAB SHALL NOT BE LIABLE FOR ANY INDIRECT, CONSEQUENTIAL, PUNITIVE, OR OTHER DAMAGES SUFFERED BY STATE OF ALASKA DEPARTMENT OF TRANSPORTATION AND PUBLIC FACILITIES, NORTH DAKOTA DEPARTMENT OF TRANSPORTATION OR ANY OTHER PERSON OR ENTITY, WHETHER SUCH LIABILITY IS BASED, OR CLAIMED TO BE BASED, UPON ANY NEGLIGENT ACT, OMISSION, ERROR, CORRECTION OF ERROR, DELAY, OR BREACH OF AN OBLIGATION BY THE TTI LAB.

1. Report No.		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle MASH TL-3 EVALUATION OF 2019 MASH 2-TUBE BRIDGE RAIL THRIE BEAM TRANSITION				5. Report Date March 2020	
				6. Performing Organization Code	
7. Author(s) William F. Williams, Wanda L. Menges, Glenn E. Schroeder, and Darrell L. Kuhn				8. Performing Organization Report No. Test Report No. 608331-01-4-6	
9. Performing Organization Name and Address Texas A&M Transportation Institute Proving Ground 3135 TAMU College Station, Texas 77843-3135				10. Work Unit No. (TRAIS)	
				11. Contract or Grant No. 1602767	
12. Sponsoring Agency Name and Address State of Alaska Department of Transportation and Public Facilities Bridge Section 3132 Channel Drive – Room 100 Juneau, AK 99811-2500				13. Type of Report and Period Covered Technical Report: February 2016 – March 2020	
				14. Sponsoring Agency Code	
15. Supplementary Notes Project Title: MASH Testing – Bridge Rail and Thrie Beam Transition Name of Contacting Representative: Elmer E. Marx – Alaska DOT&PF					
16. Abstract <p>The purpose of the tests reported herein was to assess the performance of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition according to the safety-performance evaluation guidelines included in AASHTO <i>MASH</i>. The crash tests were performed in accordance with <i>MASH</i> TL-3, which involves two full-scale crash tests (<i>MASH</i> Tests 3-20 and 3-21). However, <i>MASH</i> states that when there are transitions between two barrier types with different stiffness, one from a more flexible barrier and the other to a more rigid barrier, a full-scale crash test is recommended for both types. Therefore, <i>MASH</i> Test 3-21 was performed at the transition from the thrie beam rail to bridge rail, and at the transition from the W-beam rail to thrie beam rail.</p> <p>This report provides details of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition, detailed documentation of the crash tests and results, and an assessment of the performance of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition for <i>MASH</i> TL-3 transition evaluation criteria.</p> <p>The 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition performed acceptably for <i>MASH</i> TL-3 transitions.</p>					
17. Key Words Transition, bridge rail, thrie beam, longitudinal barrier, crash testing, MASH, roadside safety.			18. Distribution Statement Copyrighted. Not to be copied or reprinted without consent from the State of Alaska Department of Transportation and Public Facilities and North Dakota Department of Transportation.		
19. Security Classif.(of this report) Unclassified		20. Security Classif.(of this page) Unclassified		21. No. of Pages 122	22. Price

SI* (MODERN METRIC) CONVERSION FACTORS

APPROXIMATE CONVERSIONS TO SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
LENGTH				
in	inches	25.4	millimeters	mm
ft	feet	0.305	meters	m
yd	yards	0.914	meters	m
mi	miles	1.61	kilometers	km
AREA				
in ²	square inches	645.2	square millimeters	mm ²
ft ²	square feet	0.093	square meters	m ²
yd ²	square yards	0.836	square meters	m ²
ac	acres	0.405	hectares	ha
mi ²	square miles	2.59	square kilometers	km ²
VOLUME				
fl oz	fluid ounces	29.57	milliliters	mL
gal	gallons	3.785	liters	L
ft ³	cubic feet	0.028	cubic meters	m ³
yd ³	cubic yards	0.765	cubic meters	m ³
NOTE: volumes greater than 1000L shall be shown in m ³				
MASS				
oz	ounces	28.35	grams	g
lb	pounds	0.454	kilograms	kg
T	short tons (2000 lb)	0.907	megagrams (or metric ton [†])	Mg (or "t")
TEMPERATURE (exact degrees)				
°F	Fahrenheit	5(F-32)/9 or (F-32)/1.8	Celsius	°C
FORCE and PRESSURE or STRESS				
lbf	poundforce	4.45	newtons	N
lbf/in ²	poundforce per square inch	6.89	kilopascals	kPa

APPROXIMATE CONVERSIONS FROM SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
LENGTH				
mm	millimeters	0.039	inches	in
m	meters	3.28	feet	ft
m	meters	1.09	yards	yd
km	kilometers	0.621	miles	mi
AREA				
mm ²	square millimeters	0.0016	square inches	in ²
m ²	square meters	10.764	square feet	ft ²
m ²	square meters	1.195	square yards	yd ²
ha	hectares	2.47	acres	ac
km ²	Square kilometers	0.386	square miles	mi ²
VOLUME				
mL	milliliters	0.034	fluid ounces	oz
L	liters	0.264	gallons	gal
m ³	cubic meters	35.314	cubic feet	ft ³
m ³	cubic meters	1.307	cubic yards	yd ³
MASS				
g	grams	0.035	ounces	oz
kg	kilograms	2.202	pounds	lb
Mg (or "t")	megagrams (or "metric ton")	1.103	short tons (2000lb)	T
TEMPERATURE (exact degrees)				
°C	Celsius	1.8C+32	Fahrenheit	°F
FORCE and PRESSURE or STRESS				
N	newtons	0.225	poundforce	lbf
kPa	kilopascals	0.145	poundforce per square inch	lb/in ²

*SI is the symbol for the International System of Units

REPORT AUTHORIZATION

REPORT REVIEWED BY:

DocuSigned by:
Glenn Schroeder
E692F9CB5047487...
Glenn Schroeder, Research Specialist
Drafting & Reporting

DocuSigned by:
Gary Gerke
FBA2101E9F6B4B7...
Gary Gerke, Research Specialist
Construction

DocuSigned by:
Scott Dobrovolny
1C613885787C44C...
Scott Dobrovolny, Research Specialist
Mechanical Instrumentation

DocuSigned by:
Bill Griffith
44A122CB271845B...
Bill L. Griffith, Research Specialist
Deputy Quality Manager

DocuSigned by:
Matt Robinson
EAA22BFA5BFD417...
Matthew N. Robinson, Research Specialist
Test Facility Manager & Technical Manager

DocuSigned by:
Ken Reeves
60D556935596468...
Ken Reeves, Research Specialist
Electronics Instrumentation

DocuSigned by:
Richard Badillo
0F51DA60AB144F9...
Richard Badillo, Research Specialist
Photographic Instrumentation

DocuSigned by:
Wanda L. Menges
B92179622AF24FE...
Wanda L. Menges, Research Specialist
Research Evaluation and Reporting

DocuSigned by:
Darrell L. Kuhn
D4CC23E85D5B4E7...
Darrell L. Kuhn, P.E., Research Specialist
Quality Manager

DocuSigned by:
William F. Williams, P.E.
2B8AC4D2B3784AE...
William F. Williams, P.E.
Associate Research Engineer

This page intentionally left blank.

TABLE OF CONTENTS

	Page
Disclaimer	ii
List of Figures	ix
List of Tables	xi
Chapter 1. Introduction	1
1.1 Background	1
1.2 Objective	1
Chapter 2. System Details	3
2.1. Test Article and Installation Details	3
2.2. Design Modifications during Tests	3
2.3. Material Specifications	6
2.4. Soil Conditions.....	6
Chapter 3. Test Requirements and Evaluation Criteria	7
3.1. Crash Test Performed / Matrix	7
3.2. Evaluation Criteria	7
Chapter 4. Test Conditions	9
4.1. Test Facility	9
4.2 Vehicle Tow and Guidance System	9
4.3 Data Acquisition Systems	9
4.3.1 Vehicle Instrumentation and Data Processing	9
4.3.2 Anthropomorphic Dummy Instrumentation	10
4.3.3 Photographic Instrumentation Data Processing	11
Chapter 5. MASH Test 3-20 (Crash Test No. 608331-01-4)	13
5.1 Test Designation and Actual Impact Conditions	13
5.2 Weather Conditions	13
5.3 Test Vehicle	13
5.4 Test Description	14
5.5 Damage to Test Installation	14
5.6 Damage to Test Vehicle.....	15
5.7 Occupant Risk Factors	15
Chapter 6. MASH Test 3-21 at Transition from Thrie Beam to Bridge Rail (Crash Test No. 608331-01-5)	19
6.1 Test Designation and Actual Impact Conditions	19
6.2 Weather Conditions	19
6.3 Test Vehicle	19
6.4 Test Description	20
6.5 Damage to Test Installation	20
6.6 Damage to Test Vehicle.....	22
6.7 Occupant Risk Factors	22
Chapter 7. MASH Test 3-21 at Transition from W-Beam to Thrie Beam (Crash Test No. 608331-01-6)	25
7.1 Test Designation and Actual Impact Conditions	25
7.2 Weather Conditions	25

TABLE OF CONTENTS (CONTINUED)

	Page
7.3 Test Vehicle	25
7.4 Test Description	26
7.5 Damage to Test Installation	26
7.6 Damage to Test Vehicle.....	29
7.7 Occupant Risk Factors	30
Chapter 8. Summary and Conclusions	33
8.1 Assessment of Test Results.....	33
8.2 Conclusions.....	33
References	39
Appendix A. Details of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition	41
Appendix B. Supporting Certification Documents	67
Appendix C. Soil Properties.....	73
Appendix D. MASH Test 3-20 (Crash Test No. 608331-01-4).....	77
D1 Vehicle Properties and Information	77
D2 Sequential Photographs.....	80
D3 Vehicle Angular Displacements	83
D4 Vehicle Accelerations	84
Appendix E. MASH Test 3-21 (Crash Test No. 608331-01-5)	87
E1 Vehicle Properties and Information	87
E2 Sequential Photographs.....	91
E3 Vehicle Angular Displacements	94
E4 Vehicle Accelerations	95
Appendix F. MASH Test 3-21 (Crash Test No. 608331-01-6)	99
F1 Vehicle Properties and Information	99
F2 Sequential Photographs.....	103
F3 Vehicle Angular Displacements	106
F4 Vehicle Accelerations	107

LIST OF FIGURES

	Page
Figure 2.1. Details of 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition.....	4
Figure 2.2. 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition prior to Testing.....	5
Figure 5.1. Transition/Test Vehicle Geometrics for Test No. 608331-01-4.	13
Figure 5.2. Test Vehicle before Test No. 608331-01-4.....	14
Figure 5.3. Transition after Test No. 608331-01-4.	16
Figure 5.4. Test Vehicle after Test No. 608331-01-4.	17
Figure 5.5. Interior of Test Vehicle after Test No. 608331-01-4.	17
Figure 5.6. Summary of Results for <i>MASH</i> Test 3-20 on 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition.	18
Figure 6.1. 2019 Transition/Test Vehicle Geometrics for Test No. 608331-01-5.	19
Figure 6.2. Test Vehicle before Test No. 608331-01-5.....	20
Figure 6.3. Transition after Test No. 608331-01-5.	21
Figure 6.4. Test Vehicle after Test No. 608331-01-5.	22
Figure 6.5. Interior of Test Vehicle after Test No. 608331-01-5.	22
Figure 6.6. Summary of Results for <i>MASH</i> Test 3-21 on 2019 MASH 2-Tube Transition from Thrie Beam to Bridge Rail.....	24
Figure 7.1. Transition/Test Vehicle Geometrics for Test No. 608331-01-6.	25
Figure 7.2. Test Vehicle before Test No. 608331-01-6.....	26
Figure 7.3. Transition after Test No. 608331-01-6.	27
Figure 7.4. Posts 1 through 5 after Test No. 608331-01-6.....	28
Figure 7.5. Posts 6 through 15 after Test No. 608331-01-6.....	29
Figure 7.6. Test Vehicle after Test No. 608331-01-6.	30
Figure 7.7. Interior of Test Vehicle after Test No. 608331-01-6.	30
Figure 7.8. Summary of Results for <i>MASH</i> Test 3-21 2019 MASH 2-Tube Transition from W-Beam to Thrie Beam.	32
Figure D.1. Sequential Photographs for Test No. 608331-01-4 (Overhead and Frontal Views).	80
Figure D.2. Sequential Photographs for Test No. 608331-01-4 (Rear View).....	82
Figure D.3. Vehicle Angular Displacements for Test No. 608331-01-4.	83
Figure D.4. Vehicle Longitudinal Accelerometer Trace for Test No. 608331-01-4 (Accelerometer Located at Center of Gravity).	84
Figure D.5. Vehicle Lateral Accelerometer Trace for Test No. 608331-01-4 (Accelerometer Located at Center of Gravity).	85
Figure D.6. Vehicle Vertical Accelerometer Trace for Test No. 608331-01-4 (Accelerometer Located at Center of Gravity).	86
Figure E.1. Sequential Photographs for Test No. 608331-01-5 (Overhead and Frontal Views).	91
Figure E.2. Sequential Photographs for Test No. 608331-01-5 (Rear View).....	93
Figure E.3. Vehicle Angular Displacements for Test No. 608331-01-5.	94
Figure E.4. Vehicle Longitudinal Accelerometer Trace for Test No. 608331-01-5 (Accelerometer Located at Center of Gravity).	95
Figure E.5. Vehicle Lateral Accelerometer Trace for Test No. 608331-01-5 (Accelerometer Located at Center of Gravity).	96

LIST OF FIGURES (CONTINUED)

	Page
Figure E.6. Vehicle Vertical Accelerometer Trace for Test No. 608331-01-5 (Accelerometer Located at Center of Gravity).	97
Figure F.1. Sequential Photographs for Test No. 608331-01-6 (Overhead and Frontal Views).	103
Figure F.2. Sequential Photographs for Test No. 608331-01-6 (Rear View).	105
Figure F.3. Vehicle Angular Displacements for Test No. 608331-01-6.	106
Figure F.4. Vehicle Longitudinal Accelerometer Trace for Test No. 608331-01-6 (Accelerometer Located at Center of Gravity).	107
Figure F.5. Vehicle Lateral Accelerometer Trace for Test No. 608331-01-6 (Accelerometer Located at Center of Gravity).	108
Figure F.6. Vehicle Vertical Accelerometer Trace for Test No. 608331-01-6 (Accelerometer Located at Center of Gravity).	109

LIST OF TABLES

		Page
Table 3.1.	Test Conditions and Evaluation Criteria Specified for <i>MASH</i> TL-3 Transitions.....	7
Table 3.2.	Evaluation Criteria Required for <i>MASH</i> TL-3 Transitions.....	8
Table 5.1.	Events during Test No. 608331-01-4.....	14
Table 5.2.	Occupant Risk Factors for Test No. 608331-01-4.....	17
Table 6.1.	Events during Test No. 608331-01-5.....	20
Table 6.2.	Occupant Risk Factors for Test No. 608331-01-5.....	23
Table 7.1.	Events during Test No. 608331-01-6.....	26
Table 7.2.	Occupant Risk Factors for Test No. 608331-01-6.....	31
Table 8.1.	Performance Evaluation Summary for <i>MASH</i> Test 3-20 on 2019 <i>MASH</i> 2-Tube Bridge Rail Thrie Beam Transition.....	34
Table 8.2.	Performance Evaluation Summary for <i>MASH</i> Test 3-21 on 2019 <i>MASH</i> 2-Tube Bridge Rail Thrie Beam Transition from Thrie Beam to Bridge Rail.....	35
Table 8.3.	Performance Evaluation Summary for <i>MASH</i> Test 3-21 on 2019 <i>MASH</i> 2-Tube Bridge Rail Thrie Beam Transition from W-Beam to Thrie Beam.....	36
Table 8.4.	Assessment Summary for <i>MASH</i> TL-3 Testing on 2019 <i>MASH</i> 2-Tube Bridge Rail Thrie Beam Transition.....	37
Table C.1.	Summary of Strong Soil Test Results for Establishing Installation Procedure.....	73
Table C.2.	Test Day Static Soil Strength Documentation for Test No. 608331-01-4.....	74
Table C.3.	Test Day Static Soil Strength Documentation for Test No. 608331-01-5.....	75
Table C.4.	Test Day Static Soil Strength Documentation for Test No. 608331-01-6.....	76
Table D.1.	Vehicle Properties for Test No. 608331-01-4.....	77
Table D.2.	Exterior Crush Measurements for Test No. 608331-01-4.....	78
Table D.3.	Occupant Compartment Measurements for Test No. 608331-01-4.....	79
Table E.1.	Vehicle Properties for Test No. 608331-01-5.....	87
Table E.2.	Measurements of Vehicle Vertical CG for Test No. 608331-01-5.....	88
Table E.3.	Exterior Crush Measurements for Test No. 608331-01-5.....	89
Table E.4.	Occupant Compartment Measurements for Test No. 608331-01-5.....	90
Table F.1.	Vehicle Properties for Test No. 608331-01-6.....	99
Table F.2.	Measurements of Vehicle Vertical CG for Test No. 608331-01-6.....	100
Table F.3.	Exterior Crush Measurements for Test No. 608331-01-6.....	101
Table F.4.	Occupant Compartment Measurements for Test No. 608331-01-6.....	102

This page intentionally left blank.

Chapter 1. INTRODUCTION

1.1 BACKGROUND

In May 1998, Texas A&M Transportation Institute contracted with the Alaska Department of Transportation to perform engineering analyses, design, and full-scale testing on the following:

- 1.) Alaska Multi-State (2-Tube) Bridge Rail (1, 2, 3).
- 2.) Alaska Multi-State Bridge Rail Thrie Beam Transition (4, 5).
- 3.) Alaska Multi-State W-Beam Transition (6, 7).

Under that project (TTI Project No. 404311), TTI researchers performed engineering analyses, developed engineering details, and performed full-scale crash testing on the Alaska Multi-State (2-Tube) Bridge Rail (1-3). The bridge rail successfully met the performance requirements of National Cooperative Highway Research Program (NCHRP) *Report 350* Test Level 4 (TL-4) (8). TTI researchers evaluated the strength and performance of a new, taller Alaska Multi-State 2-Tube Bridge Rail, herein after it was re-designated as the 2019 MASH 2-Tube Bridge Rail, with respect to American Association of State Highway and Transportation Officials (AASHTO) Manual for Assessing Safety Hardware (*MASH*), Second Edition 2016, specifications (9, 10). TTI researchers performed engineering analyses and developed engineering details for this design to meet the performance requirements of *MASH* TL-4. TTI Proving Ground performed full-scale crash testing on the 2019 MASH 2-Tube Bridge Rail with respect to *MASH* TL-4, and the bridge rail performed acceptably.

1.2 OBJECTIVE

As part of this current project, TTI researchers performed analyses, designed, and full-scale tested a new Alaska Multi-State Bridge Rail Thrie Beam Transition. This new thrie beam transition design was tested with respect to *MASH* TL-3.

The purpose of the tests reported herein was to assess the performance of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition according to the safety-performance evaluation guidelines included in AASHTO *MASH*. The crash tests were performed in accordance with *MASH* TL-3, which involves two full-scale crash tests (*MASH* Tests 3-20 and 3-21). However, *MASH* states that when there are transitions between two barrier types with different stiffness, one from a more flexible barrier and the other to a more rigid barrier, a full-scale crash test is recommended for both types. Therefore, *MASH* Test 3-21 was performed at the transition from the thrie beam rail to bridge rail, and at the transition from the W-beam rail to thrie beam rail.

This report provides details of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition, detailed documentation of the three crash tests and results, and an assessment of the performance of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition for *MASH* TL-3 evaluation criteria.

This page intentionally left blank.

Chapter 2. SYSTEM DETAILS

2.1. TEST ARTICLE AND INSTALLATION DETAILS

The 2019 MASH 2-Tube Bridge Rail test installation was comprised of a 154-ft long section of reinforced concrete bridge deck that incorporated two steel rails, a 12½-ft long (nominal) section of two nested thrie beams (RTM08a) attached to the bridge rails with a thrie beam terminal connector (RTE01b) and unique guardrail connector, a standard symmetrical 75-inch long (nominal) thrie-beam-to-W-beam transition rail section (RWT01b), 25 ft of W-beam guardrail (in length of need), and a standard 9 ft-4½ inch long TxDOT DAT terminal (posts 1 and 2) at the end.

The total length of the installation was approximately 207 ft-3½ inches (53 ft-3½ inches transition + 154 ft bridge deck). The top edges of the DAT rail and W-beam were located 31 inches above grade. The top edge of the nested thrie beam was 34¾ inches above grade, and the top of the upper bridge rail was 38 inches above the bridge deck.

Posts 3 through 6 were 72 inches long (embedded 40 inches), posts 7 and 8 were 72 inches long, and posts 9 through 15 were 78 inches long. Posts 1 through 6 were spaced at 75 inches; posts 7 through 10 were at 37½ inches; and posts 10 through 15 were at 18¾ inches. Timber blockouts, 8-inches deep, were installed on posts 2 through 6. Posts 7 and 8 were fitted with 12-inch deep, short (14 inches) steel hollow structural section (HSS) tubing blockouts, and posts 9 through 15 were fitted with 12-inch deep, long (21⅛ inches) steel HSS blockouts,


The concrete portion of the 2019 MASH 2-Tube Bridge Rail test installation consisted of a reinforced cantilevered deck and curb, with two 2-inch wide joints extending through both the curb and the deck. The curb was 10 inches tall, with a 4-inch thick lift of grout, yielding a 6-inch tall traffic side face. The curb was 18 inches wide at the base, and 17 inches wide at the top, with the traffic side face sloping 1-inch toward the field side. Anchor bolts were cast in the deck and extended through the curb.

Sixteen fabricated steel posts were longitudinally spaced on 10 ft centers, beginning at 24 inches from each end of the concrete curb. Two steel rectangular HSS rail elements spanned the posts and extended past them at each end of the installation. The tops of the rails were located 24 inches and 38 inches above grade.

Figure 2.1 presents overall information on the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition, and Figure 2.2 provides photographs of the installation. Appendix A provides further details of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition.

2.2. DESIGN MODIFICATIONS DURING TESTS

No modification was made to the installation during the testing phase.



T:\1-ProjectFiles\608331- Alaska - Williams\Drafting_608331 4-5\608331 4-6 Drawing

Figure 2.1. Details of 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition.



Figure 2.2. 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition prior to Testing.

2.3. MATERIAL SPECIFICATIONS

The specified minimum unconfined compressive strength of the concrete was 4000 psi for the curb, and 5000 psi for the deck. On December 10, 2018 (date of the first test on the 2-Tube Bridge Rail and deck), the average compressive strength of the concrete was 5060 psi (at 42 days) for the curb, and 5670 psi (at 44 days) for the deck.

Appendix B provides material certification documents for the materials used to install/construct the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition.

2.4. SOIL CONDITIONS

The transition and terminal of the test installation were installed in soil meeting grading B of AASHTO standard specification M147 “Materials for Aggregate and Soil Aggregate Subbase, Base and Surface Courses.”

In accordance with Appendix B of *MASH*, soil strength was measured the day of the crash test. During installation of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition for full-scale crash testing, two 6-ft long W6×16 posts were installed in the immediate vicinity of the transition using the same fill materials and installation procedures used in the test installation and the standard dynamic test. Table C.1 in Appendix C presents minimum soil strength properties established through the dynamic testing performed in accordance with *MASH* Appendix B.

As determined by the tests summarized in Appendix C, Table C.1, the minimum post loads required for deflections at 5 inches, 10 inches, and 15 inches, measured at a height of 25 inches, are 3940 lb, 5500 lb, and 6540 lb, respectively (90 percent of static load for the initial standard installation).

On the day of Test No. 608331-01-4, September 2, 2019, loads on the post at deflections of 5 inches, 10 inches, and 15 inches were 9087 lbf, 9948 lbf, and 10,395 lbf. Table C.2 in Appendix C shows the strength of the backfill material in which the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition was installed met minimum *MASH* requirements.

On the day of Test No. 608331-01-5, September 5, 2019, load on the post at 5 inches of deflection was 11,359 lbf, which was almost triple the required load. It was determined during the test pull that any additional loading may impart stresses on the W6×16 post that could cause it to yield and bend, or could cause damage to the test pull equipment (e.g. winch, load cell, etc.) Therefore, the test was terminated and the loads at deflections of 10 inches and 15 inches were not measured. Table C.3 in Appendix C shows the strength of the backfill material in which the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition was installed met minimum *MASH* requirements.

On the day of Test No. 608331-01-6, December 19, 2019, loads on the post at deflections of 5 inches, 10 inches, and 15 inches were 9225 lbf, 8537 lbf, and 7504 lbf. Table C.2 in Appendix C shows the strength of the backfill material in which the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition was installed met minimum *MASH* requirements.

Chapter 3. TEST REQUIREMENTS AND EVALUATION CRITERIA

3.1. CRASH TEST PERFORMED / MATRIX

Table 3.1 shows the test conditions and evaluation criteria recommended for *MASH* TL-3 transitions. However, *MASH* states that when there are transitions between two barrier types with different stiffness, one from a more flexible barrier and the other to a more rigid barrier, a full-scale crash test is recommended for both types. Therefore, *MASH* Test 3-21 was performed at the transition from the thrie beam rail to bridge rail, and at the transition from the W-beam rail to thrie beam rail.

Table 3.1. Test Conditions and Evaluation Criteria Specified for *MASH* TL-3 Transitions.

Test Article	Test Designation	Test Vehicle	Impact Conditions		Evaluation Criteria
			Speed	Angle	
Transitions	3-20	1100C	62 mi/h	25°	A, D, F, H, I
	3-21	2270P	62 mi/h	25°	A, D, F, H, I

The target critical impact point (CIP) for each test was determined in accordance with the guidance provided in *MASH Section 2.3.2* and *MASH Figure 2-1*. For *MASH* Test 3-20, the target CIP was 5.1 ft upstream of the end of the concrete curb/deck. The target CIP for *MASH* Test 3-21 on the thrie beam to bridge rail transition was 7.0 ft upstream of the concrete curb/deck. The target CIP for *MASH* Test 3-21 on the W-beam to thrie beam transition was 7.3 ft upstream of the centerline of post 7. TTI researchers determined that *MASH* Test 3-20 on the W-beam to thrie beam transition was not necessary and was therefore not performed.

The crash tests and data analysis procedures were in accordance with guidelines presented in *MASH*. Chapter 4 presents brief descriptions of these procedures.

3.2. EVALUATION CRITERIA

The appropriate safety evaluation criteria from Tables 2-2 and 5-1 of *MASH* were used to evaluate the crash tests reported herein. The test conditions and evaluation criteria required for *MASH* TL-3 transitions are listed in Table 3.1, and the substance of the evaluation criteria in Table 3.2. An evaluation of the crash test results is presented in detail under the section Assessment of Test Results.

Table 3.2. Evaluation Criteria Required for MASH TL-3 Transitions.

Evaluation Factors	Evaluation Criteria
Structural Adequacy	<p>A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i></p>
Occupant Risk	<p>D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present undue hazard to other traffic, pedestrians, or personnel in a work zone.</i></p> <p><i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i></p>
	<p>F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i></p>
	<p>H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i></p>
	<p>I. <i>The occupant ridedown accelerations should satisfy the following: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i></p>

Chapter 4. TEST CONDITIONS

4.1. TEST FACILITY

The full-scale crash tests reported herein were performed at Texas A&M Transportation Institute (TTI) Proving Ground, an International Standards Organization (ISO)/International Electrotechnical Commission (IEC) 17025-accredited laboratory with American Association for Laboratory Accreditation (A2LA) Mechanical Testing Certificate 2821.01. The full-scale crash tests were performed according to TTI Proving Ground quality procedures, and according to the *MASH* guidelines and standards.

The test facilities of the TTI Proving Ground are located on the Texas A&M University System RELLIS Campus, which consists of a 2000-acre complex of research and training facilities situated 10 miles northwest of the flagship campus of Texas A&M University. The site, formerly a United States Army Air Corps base, has large expanses of concrete runways and parking aprons well suited for experimental research and testing in the areas of vehicle performance and handling, vehicle-roadway interaction, durability and efficacy of highway pavements, and evaluation of roadside safety hardware and perimeter protective devices. The site selected for construction and testing of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition was along the edge of an out-of-service apron. The apron consists of an unreinforced jointed-concrete pavement in 12.5-ft × 15-ft blocks nominally 6 inches deep. The aprons were built in 1942, and the joints have some displacement, but are otherwise flat and level.

4.2 VEHICLE TOW AND GUIDANCE SYSTEM

Each test vehicle was towed into the test installation using a steel cable guidance and reverse tow system. A steel cable for guiding the test vehicle was tensioned along the path, anchored at each end, and threaded through an attachment to the front wheel of the test vehicle. An additional steel cable was connected to the test vehicle, passed around a pulley near the impact point, through a pulley on the tow vehicle, and then anchored to the ground such that the tow vehicle moved away from the test site. A 2:1 speed ratio between the test and tow vehicle existed with this system. Just prior to impact with the installation, the test vehicle was released and ran unrestrained. The vehicle remained freewheeling (i.e., no steering or braking inputs) until it cleared the immediate area of the test site (no sooner than 2 s after impact), after which the brakes were activated, if needed, to bring the test vehicle to a safe and controlled stop.

4.3 DATA ACQUISITION SYSTEMS

4.3.1 Vehicle Instrumentation and Data Processing

Each test vehicle was instrumented with a self-contained, on-board data acquisition system. The signal conditioning and acquisition system is a 16-channel, Tiny Data Acquisition System (TDAS) Pro produced by Diversified Technical Systems, Inc. The accelerometers, which measure the x, y, and z axis of vehicle acceleration, are strain gauge type with linear millivolt output proportional to acceleration. Angular rate sensors, measuring vehicle roll, pitch, and yaw rates, are ultra-small, solid state units designed for crash test service. The TDAS Pro hardware

and software conform to the latest SAE J211, Instrumentation for Impact Test. Each of the 16 channels is capable of providing precision amplification, scaling, and filtering based on transducer specifications and calibrations. During the test, data are recorded from each channel at a rate of 10,000 samples per second with a resolution of one part in 65,536. Once data are recorded, internal batteries back these up inside the unit should the primary battery cable be severed. Initial contact of the pressure switch on the vehicle bumper provides a time zero mark and initiates the recording process. After each test, the data are downloaded from the TDAS Pro unit into a laptop computer at the test site. The Test Risk Assessment Program (TRAP) software then processes the raw data to produce detailed reports of the test results.

Each of the TDAS Pro units is returned to the factory annually for complete recalibration and all instrumentation used in the vehicle conforms to all specifications outlined by SAE J211. All accelerometers are calibrated annually by means of an ENDEVCO® 2901, precision primary vibration standard. This standard and its support instruments are checked annually and receive a National Institute of Standards Technology (NIST) traceable calibration. The rate transducers used in the data acquisition system receive a calibration via a Genisco Rate-of-Turn table. The subsystems of each data channel are also evaluated annually, using instruments with current NIST traceability, and the results are factored into the accuracy of the total data channel, per SAE J211. Calibrations and evaluations are also made any time data are suspect. Acceleration data are measured with an expanded uncertainty of ± 1.7 percent at a confidence factor of 95 percent ($k=2$).

TRAP uses the data from the TDAS Pro to compute occupant/compartment impact velocities, time of occupant/compartment impact after vehicle impact, and the highest 10-millisecond (ms) average ridedown acceleration. TRAP calculates change in vehicle velocity at the end of a given impulse period. In addition, maximum average accelerations over 50-ms intervals in each of the three directions are computed. For reporting purposes, the data from the vehicle-mounted accelerometers are filtered with an SAE Class 180-Hz low-pass digital filter, and acceleration versus time curves for the longitudinal, lateral, and vertical directions are plotted using TRAP.

TRAP uses the data from the yaw, pitch, and roll rate transducers to compute angular displacement in degrees at 0.0001-s intervals, then plots yaw, pitch, and roll versus time. These displacements are in reference to the vehicle-fixed coordinate system with the initial position and orientation of the vehicle-fixed coordinate systems being initial impact. Rate of rotation data is measured with an expanded uncertainty of ± 0.7 percent at a confidence factor of 95 percent ($k=2$).

4.3.2 Anthropomorphic Dummy Instrumentation

An Alderson Research Laboratories Hybrid II, 50th percentile male anthropomorphic dummy, restrained with lap and shoulder belts, was placed in the front seat on the impact side of the 1100C vehicle. The dummy was not instrumented.

According to *MASH*, use of a dummy in the 2270P vehicle is optional. However, it is recommended a dummy be used when testing “any longitudinal barrier with a height greater than or equal to 33 inches.” Use of the dummy in the 2270P vehicle is recommended for tall rails to

evaluate the “potential for an occupant to extend out of the vehicle and come into direct contact with the test article.” Although this information is reported, it is not part of the impact performance evaluation. Since the rail height of the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition was 34¾ inches, a dummy was placed in the front seat of the 2270P vehicle on the impact side and restrained with lap and shoulder belts.

A dummy was not used in *MASH* Test 3-21 test of the W-beam to thrie beam transition as the rail height at impact was 31 inches.

4.3.3 Photographic Instrumentation Data Processing

Photographic coverage of each test included three digital high-speed cameras:

- One overhead with a field of view perpendicular to the ground and directly over the impact point;
- One placed behind the installation at an angle; and
- A third placed to have a field of view parallel to and aligned with the installation at the downstream end.

A flashbulb on the impacting vehicle was activated by a pressure-sensitive tape switch to indicate the instant of contact with the transition. The flashbulb was visible from each camera. The video files from these digital high-speed cameras were analyzed to observe phenomena occurring during the collision and to obtain time-event, displacement, and angular data. A digital camera recorded and documented conditions of each test vehicle and the installation before and after the test.

This page intentionally left blank.

Chapter 5. MASH TEST 3-20 (CRASH TEST NO. 608331-01-4)

5.1 TEST DESIGNATION AND ACTUAL IMPACT CONDITIONS

MASH Test 3-20 involves an 1100C vehicle weighing 2420 lb \pm 55 lb impacting the CIP of the transition at an impact speed of 62 mi/h \pm 2.5 mi/h and an angle of 25° \pm 1.5°. The target CIP for MASH Test 3-20 on the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition was 5.10 ft \pm 1 ft upstream of the end of the concrete curb/deck. Figure 5.1 depicts the target CIP.



Figure 5.1. Transition/Test Vehicle Geometrics for Test No. 608331-01-4.

The 2007 Kia Rio* used in the test weighed 2446 lb, and the actual impact speed and angle were 60.9 mi/h and 26.5°, respectively. The actual impact point was 6.06 ft upstream of the end of the concrete curb/deck. Minimum target impact severity (IS) was 51 kip-ft, and actual IS was 61 kip-ft.

5.2 WEATHER CONDITIONS

The test was performed on the morning of September 2, 2019. Weather conditions at the time of testing were as follows: wind speed: 4 mi/h; wind direction: 105° (vehicle was traveling at magnetic heading of 335°); temperature: 93°F; relative humidity: 53 percent.

5.3 TEST VEHICLE

Figures 5.1 and 5.2 show the 2007 Kia Rio used for the crash test. The vehicle's test inertia weight was 2446 lb, and its gross static weight was 2611 lb. The height to the lower edge of the vehicle bumper was 7.75 inches, and height to the upper edge of the bumper was 21.5 inches. Table D.1 in Appendix D1 gives additional dimensions and information on the

* The 2007 model vehicle used is older than the 6-year age noted in MASH, and was selected based upon availability. An older model vehicle is permitted by AASHTO as long as it is otherwise MASH compliant. Other than the vehicle's year model, this 2007 model vehicle met the MASH requirements.

vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.



Figure 5.2. Test Vehicle before Test No. 608331-01-4.

5.4 TEST DESCRIPTION

The test vehicle was traveling at an impact speed of 60.9 mi/h when it contacted the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition 6.06 ft upstream of the end of the concrete curb/deck at an impact angle of 26.5°. Table 5.1 lists events that occurred during Test No. 608331-01-4. Figures D.1 and D.2 in Appendix D2 present sequential photographs during the test.

Table 5.1. Events during Test No. 608331-01-4.

TIME (s)	EVENTS
0.000	Vehicle contacts transition
0.023	Vehicle begins to redirect
0.091	Vehicle makes a slight increase in clockwise yaw rate
0.234	Vehicle traveling parallel with transition
0.355	Left rear corner and bumper of vehicle contacts transition
0.447	Vehicle loses contact with transition while traveling at 39.5 mi/h, trajectory of 7.1°, and heading of 14.0°

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. After loss of contact with the transition, the vehicle came to rest 145 ft downstream of the impact point and 137 ft toward the traffic lanes.

5.5 DAMAGE TO TEST INSTALLATION

Figure 5.3 shows the damage to the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition. Posts 12 through 15 were leaning back at 89°, and the soil was disturbed around each

of those posts. There was no visible soil disturbance at posts 1 and 2. The bottom edge of the thrie beam rail was deformed in the impact area, and the concrete deck cracked at post 16 (the first post on the bridge deck). Working width* was 26.1 inches, and height of working width was 34.75 inches. Maximum dynamic deflection during the test was 3.5 inches, and maximum permanent deformation was 1.25 inches.

5.6 DAMAGE TO TEST VEHICLE

Figure 5.4 shows the damage sustained by the vehicle. The front bumper, hood, grill, radiator and support, left front strut and tower, left lower control arm, left front tire and rim, left front fender, left front door and glass, left front floor pan, and left rear quarter panel were damaged. No fuel tank damage was observed. The windshield sustained stress cracks from displacement of the left A-pillar, and the roof was slightly deformed. A small hole in the windshield was caused by the impact of the hood. Maximum exterior crush to the vehicle was 14.0 inches in the side plane at the left front corner at bumper height. Maximum occupant compartment deformation was 3.5 inches in the left kick panel area. Figure 5.5 shows the interior of the vehicle. Tables D.3 and D.4 in Appendix D1 provide exterior crush and occupant compartment measurements.

5.7 OCCUPANT RISK FACTORS

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in Table 5.2. Figure D.3 in Appendix D3 shows the vehicle angular displacements, and Figures D.4 through D.6 in Appendix D4 show acceleration versus time traces. Figure 5.6 summarizes pertinent information from the test.

* Per *MASH*, "The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article." In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.



Figure 5.3. Transition after Test No. 608331-01-4.





Figure 5.4. Test Vehicle after Test No. 608331-01-4.



Figure 5.5. Interior of Test Vehicle after Test No. 608331-01-4.

Table 5.2. Occupant Risk Factors for Test No. 608331-01-4.

Occupant Risk Factor	Value	Time
Occupant Impact Velocity (OIV)		
Longitudinal	22.6 ft/s	at 0.0824 s on left side of interior
Lateral	30.5 ft/s	
Occupant Ridedown Accelerations		
Longitudinal	14.5 g	0.0975 - 0.1075 s
Lateral	9.2 g	0.0940 - 0.1040 s
Theoretical Head Impact Velocity (THIV)	41.0 km/h 11.4 m/s	at 0.0805 s on left side of interior
Acceleration Severity Index (ASI)	2.17	0.0496 - 0.0996 s
Maximum 50-ms Moving Average		
Longitudinal	-12.0 g	0.0292 - 0.0792 s
Lateral	16.8 g	0.0303 - 0.0803 s
Vertical	-3.6 g	0.0850 - 0.1350 s
Maximum Roll, Pitch, and Yaw Angles		
Roll	12°	1.9987 s
Pitch	3°	2.0000 s
Yaw	63°	1.5386 s



General Information

Test Agency..... Texas A&M Transportation Institute (TTI)
 Test Standard Test No. MASH Test 3-20
 TTI Test No. 608331-01-4
 Test Date 2019-09-02

Test Article

Type Transition
 Name 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Installation Length 207 ft 3½ inches (incl 154 ft of deck)
 Material or Key Elements ... Thrie beam guardrail terminal to 38-inch tall 2-tube bridge rail, 34¾ inch tall thrie beam guardrail section, symmetrical W-beam to thrie beam terminal, 25 ft of W-beam guardrail

Soil Type and Condition

..... AASHTO M147 Grading B Soil (crushed limestone), Damp

Test Vehicle

Type/Designation 1100C
 Make and Model 2007 Kia Rio
 Curb 2470 lb
 Test Inertial 2446 lb
 Dummy 165 lb
 Gross Static 2611 lb

Impact Conditions

Speed 60.9 mi/h
 Angle 26.5°
 Location/Orientation 6.06 ft upstream of end of curb/deck

Impact Severity

..... 61 kip-ft

Exit Conditions

Speed 39.5 mi/h
 Trajectory/Heading Angle... 7.1° / 14.0°

Occupant Risk Values

Longitudinal OIV 22.6 ft/s
 Lateral OIV 30.5 ft/s
 Longitudinal Ridedown 14.5 g
 Lateral Ridedown 9.2 g
 THIV 41.0 km/h
 ASI 2.17

Max. 0.050-s Average

Longitudinal -12.0 g
 Lateral 16.8 g
 Vertical -3.6 g

Post-Impact Trajectory

Stopping Distance 145 ft downstream
 137 ft twd traffic

Vehicle Stability

Maximum Yaw Angle 63°
 Maximum Pitch Angle 3°
 Maximum Roll Angle 12°
 Vehicle Snagging No
 Vehicle Pocketing No

Test Article Deflections

Dynamic 3.5 inches
 Permanent 1.25 inches
 Working Width 26.1 inches
 Height of Working Width 34.75 inches

Vehicle Damage

VDS 11LFQ6
 CDC 11FLEW5
 Max. Exterior Deformation 14.0 inches
 OCDI FL0010000
 Max. Occupant Compartment Deformation 3.5 inches

Figure 5.6. Summary of Results for MASH Test 3-20 on 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition.

Chapter 6. *MASH* TEST 3-21 AT TRANSITION FROM THRIE BEAM TO BRIDGE RAIL (CRASH TEST NO. 608331-01-5)

6.1 TEST DESIGNATION AND ACTUAL IMPACT CONDITIONS

MASH Test 3-21 involves a 2270P vehicle weighing 5000 lb \pm 110 lb impacting the CIP of the transition at an impact speed of 62 mi/h \pm 2.5 mi/h and an angle of 25° \pm 1.5°. The target CIP for *MASH* Test 3-21 on the 2019 *MASH* 2-Tube Bridge Rail Thrie Beam Transition was 7.00 ft \pm 1 ft upstream of the end of the concrete curb/deck. Figure 6.1 depicts the target CIP.



Figure 6.1. 2019 Transition/Test Vehicle Geometrics for Test No. 608331-01-5.

The 2013 RAM 1500 pickup truck used in the test weighed 5050 lb, and the actual impact speed and angle were 61.9 mi/h and 25.3°, respectively. The actual impact point was 6.52 ft upstream of the end of the concrete curb/deck. Minimum target IS was 106 kip-ft, and actual IS was 118 kip-ft.

6.2 WEATHER CONDITIONS

The test was performed on the morning of September 5, 2019. Weather conditions at the time of testing were as follows: wind speed: 2 mi/h; wind direction: 244° (vehicle was traveling at magnetic heading of 335°); temperature: 91°F; relative humidity: 57 percent.

6.3 TEST VEHICLE

Figures 6.1 and 6.2 show the 2013 RAM 1500 pickup truck used for the crash test. The vehicle's test inertia weight was 5050 lb, and its gross static weight was 5215 lb. The height to the lower edge of the vehicle bumper was 11.75 inches, and height to the upper edge of the bumper was 27.0 inches. The height to the vehicle's center of gravity was 28.25 inches. Tables E.1 and E.2 in Appendix E1 give additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.



Figure 6.2. Test Vehicle before Test No. 608331-01-5.

6.4 TEST DESCRIPTION

The test vehicle was traveling at an impact speed of 61.9 mi/h when it contacted the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition 6.52 ft upstream of the end of the concrete curb/deck at an impact angle of 25.3°. Table 6.1 lists events that occurred during Test No. 608331-01-5. Figures E.1 and E.2 in Appendix E2 present sequential photographs during the test.

Table 6.1. Events during Test No. 608331-01-5.

TIME (s)	EVENTS
0.000	Vehicle contacts transition
0.035	Vehicle begins to redirect
0.149	Right front tire leaves the pavement
0.210	Vehicle traveling parallel with transition
0.207	Left rear bumper and corner of vehicle contacts transition
0.377	Vehicle loses contact with transition while traveling at 47.9 mi/h, trajectory of 6.9°, and heading of 6.5°

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. Brakes on the vehicle were applied at 3.0 s after impact, and the vehicle subsequently came to rest 174 ft downstream of the impact point.

6.5 DAMAGE TO TEST INSTALLATION

Figure 6.3 shows the damage to the 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition. There was no visible indication of movement at posts 1 through 10. The soil was disturbed around post 10, and posts 10, 11, and 12 were leaning 89° toward the field side. There was a 0.5-inch gap in the soil on the traffic side of post 12. Posts 13-15 were leaning slightly toward field side, posts 13 and 15 had an 0.5-inch gap between the posts and soil on the traffic

and field sides, and post 14 on the field side only. Working width* was 26.9 inches, and height of working width was 34.75 inches. Maximum dynamic deflection during the test was 6.1 inches, and maximum permanent deformation was 3.75 inches.



Figure 6.3. Transition after Test No. 608331-01-5.

* Per *MASH*, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.

6.6 DAMAGE TO TEST VEHICLE

Figure 6.4 shows the damage sustained by the vehicle. The front bumper, hood, grill, radiator and support, left front fender, left front tire and rim, left upper and lower A-arms, left front door and window glass, left front floor pan, left rear door, left rear cab corner, left rear exterior bed, left rear rim, and rear bumper were damaged. No fuel tank damage was observed. Maximum exterior crush to the vehicle was 15.0 inches in the side plane at the left front at bumper height. Maximum occupant compartment deformation was 4.0 inches in the left side kick panel. Figure 5.5 shows the interior of the vehicle. Tables E.3 and E.4 in Appendix E1 provide exterior crush and occupant compartment measurements.



Figure 6.4. Test Vehicle after Test No. 608331-01-5.




Figure 6.5. Interior of Test Vehicle after Test No. 608331-01-5.

6.7 OCCUPANT RISK FACTORS

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in Table 6.2. Figure E.3 in Appendix E3 shows the vehicle angular displacements, and Figures E.4 through E.6 in Appendix E4 show acceleration versus time traces. Figure 6.6 summarizes pertinent information from the test.

Table 6.2. Occupant Risk Factors for Test No. 608331-01-5.

Occupant Risk Factor	Value	Time
OIV Longitudinal Lateral	20.3 ft/s 23.6 ft/s	at 0.1075 s on left side of interior
Occupant Ridedown Accelerations Longitudinal Lateral	7.4 g 13.0 g	0.1313 - 0.1413 s 0.2459 - 0.2559 s
THIV	9.3 m/s	at 0.1042 s on left side of interior
ASI	1.51	0.0598 - 0.1098 s
Maximum 50-ms Moving Average Longitudinal Lateral Vertical	-8.7 g 10.9 g -4.7 g	0.0477 - 0.0977 s 0.0386 - 0.0886 s 0.0572 - 0.1072 s
Maximum Roll, Pitch, and Yaw Angles Roll Pitch Yaw	8° 11° 43°	1.1616 s 1.9957 s 0.8706 s



General Information

Test Agency..... Texas A&M Transportation Institute (TTI)
 Test Standard Test No..... MASH Test 3-21
 TTI Test No. 608331-01-5
 Test Date 2019-09-05

Test Article

Type Transition
 Name..... 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Installation Length..... 207 ft 3½ inches (incl 154 ft of deck)
 Material or Key Elements... Thrie beam guardrail terminal to 38-inch tall 2-tube bridge rail, 34¾ inch tall thrie beam guardrail section, symmetrical W-beam to thrie beam terminal, 25 ft of W-beam guardrail

Soil Type and Condition

..... AASHTO M147 Grading B Soil (crushed limestone), Damp

Test Vehicle

Type/Designation..... 2270P
 Make and Model 2013 RAM 1500 Pickup
 Curb..... 5168 lb
 Test Inertial..... 5050 lb
 Dummy 165 lb
 Gross Static 5215 lb

Impact Conditions

Speed 61.9 mi/h
 Angle 25.3°
 Location/Orientation 6.52 ft upstream of end of curb/deck

Impact Severity

..... 118 kip-ft

Exit Conditions

Speed 47.9 mi/h
 Trajectory/Heading Angle... 6.9° / 6.5°

Occupant Risk Values

Longitudinal OIV 20.3 ft/s
 Lateral OIV..... 23.6 ft/s
 Longitudinal Ridedown 7.4 g
 Lateral Ridedown 13.0 g
 THIV 33.5 km/h
 ASI..... 1.51
 Max. 0.050-s Average
 Longitudinal -8.7 g
 Lateral..... 10.9 g
 Vertical..... -4.7 g

Post-Impact Trajectory

Stopping Distance..... 174 ft downstream
 Aligned w/traffic face

Vehicle Stability

Maximum Yaw Angle 43°
 Maximum Pitch Angle 11°
 Maximum Roll Angle 8°
 Vehicle Snagging..... No
 Vehicle Pocketing No

Test Article Deflections

Dynamic..... 6.1 inches
 Permanent 3.75 inches
 Working Width..... 26.9 inches
 Height of Working Width 34.75 inches

Vehicle Damage

VDS 11LFQ5
 CDC..... 11FLEW4
 Max. Exterior Deformation..... 15.0 inches
 OCDI..... FL0011000
 Max. Occupant Compartment Deformation 4.0 inches

Figure 6.6. Summary of Results for MASH Test 3-21 on 2019 MASH 2-Tube Transition from Thrie Beam to Bridge Rail.

Chapter 7. MASH TEST 3-21 AT TRANSITION FROM W-BEAM TO THRIE BEAM (CRASH TEST NO. 608331-01-6)

7.1 TEST DESIGNATION AND ACTUAL IMPACT CONDITIONS

MASH Test 3-21 involves a 2270P vehicle weighing 5000 lb \pm 110 lb impacting the CIP of the transition at an impact speed of 62 mi/h \pm 2.5 mi/h and an angle of 25° \pm 1.5°. The target CIP for *MASH* Test 3-21 on the 2019 *MASH* 2-Tube Bridge Rail Thrie Beam Transition was 7.3 ft \pm 1 ft upstream of the centerline of post 7. Figure 7.1 depicts the target CIP.



Figure 7.1. Transition/Test Vehicle Geometrics for Test No. 608331-01-6.

The 2013 RAM 1500 used in the test weighed 5038 lb, and the actual impact speed and angle were 62.6 mi/h and 24.9°. The actual impact point was 7.5 ft upstream of the centerline of post 7. Minimum target IS was 106 kip-ft, and actual IS was 117 kip-ft.

7.2 WEATHER CONDITIONS

The test was performed on the morning of December 19, 2019. Weather conditions at the time of testing were as follows: wind speed: 1 mi/h; wind direction: 140° (vehicle was traveling at magnetic heading of 335°); temperature: 45°F; relative humidity: 66 percent.

7.3 TEST VEHICLE

Figure 7.2 shows the 2013 RAM 1500 pickup truck used for the crash test. The vehicle's test inertia weight was 5038 lb, and its gross static weight was 5038 lb. The height to the lower edge of the vehicle bumper was 11.75 inches, and height to the upper edge of the bumper was 27.0 inches. The height to the vehicle's center of gravity was 29.0 inches. Tables F.1 and F.2 in Appendix F1 give additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.



Figure 7.2. Test Vehicle before Test No. 608331-01-6.

7.4 TEST DESCRIPTION

Table 7.1 lists events that occurred during Test No. 608331-01-6. Figures F.1 and F.2 in Appendix F2 present sequential photographs during the test.

Table 7.1. Events during Test No. 608331-01-6.

TIME (s)	EVENTS
0.000	Vehicle contacts transition
0.017	Post 5 and 6 begin to deflect toward protected side
0.028	Vehicle begins to redirect
0.028	Post 7 begins to deflect toward protected side
0.053	Post 4 begins to rotate counter-clockwise
0.125	Right front tire lifts off pavement
0.203	Right rear tire lifts off pavement
0.284	Vehicle is traveling parallel with transition
0.609	Vehicle loses contact with transition while traveling at 31.8 mi/h, trajectory of 23.3°, and heading of 24.7°
0.776	Right front tire makes contact with pavement
0.885	Left rear tire makes contact with pavement

For longitudinal barriers, it is desirable that the vehicle redirects and exits the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. Brakes on the vehicle were applied at 3.5 s after impact. After loss of contact with the barrier, the vehicle came to rest 133 ft downstream of the impact and 2 ft toward traffic lanes.

7.5 DAMAGE TO TEST INSTALLATION

Figures 7.3 through 7.5 show the damage to the transition. The metal rail element released from posts 1-5 and 7-10. Post 1 was pulled downstream 0.75 inch and post 2 was split.

Post 5 was leaning toward field side 88°, and there was a gap between the soil and post of 0.5 inch on the field side and 1.0 inch on the traffic side. Post 6 was leaning toward field side 76°, and there was a gap between the soil and post of 1.5 inches on the field side and 6.0 inches on the traffic side. Posts 7 through 9 were pushed toward field side and downstream. Post 10 was leaning toward field side 80°, and the gap between the soil and post was 3.0 inches on the field side and 0.75 inch on the traffic side. Post 11 was leaning toward field side 84°, and the gap between the soil and post was 3.0 inches on the field side. Post 12 was leaning toward field side 87°, and the gap between the post and soil was 0.13 inches on the traffic side and 1.5 inches on the field side. Post 13 was leaning toward field side 88°, and the post was pushed toward field side 0.75 inch. Post 14 was pushed toward field side 0.5 inch, and the soil around post 15 was disturbed only. Working width* was 44.7 inches, and height of working width was 61.8 inches. Maximum dynamic deflection during the test was 33.6 inches, and maximum permanent deformation was 28.0 inches.



Figure 7.3. Transition after Test No. 608331-01-6.

* Per *MASH*, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.



Figure 7.4. Posts 1 through 5 after Test No. 608331-01-6.



Figure 7.5. Posts 6 through 15 after Test No. 608331-01-6.

7.6 DAMAGE TO TEST VEHICLE

Figure 7.6 shows the damage sustained by the vehicle. The front bumper, radiator and support, hood, grill, left front fender, left frame rail, left upper and lower control arms, left front tire and rim, left front door, left rear exterior bed, left rear rim, and rear bumper were damaged. No fuel tank damage was observed. The windshield showed stress cracks radiating upward and inward from the lower left A-post. Maximum exterior crush to the vehicle was 20.0 inches in the side plane at the left front corner at bumper height. No occupant compartment deformation or intrusion was observed. Figure 7.7 shows the interior of the vehicle. Tables F.3 and F.4 in Appendix F1 provide exterior crush and occupant compartment measurements.




Figure 7.6. Test Vehicle after Test No. 608331-01-6.




Figure 7.7. Interior of Test Vehicle after Test No. 608331-01-6.

7.7 OCCUPANT RISK FACTORS

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in Table 7.2. Figure F.3 in Appendix F3 shows the vehicle angular displacements, and Figures F.4 through F.6 in Appendix F4 show acceleration versus time traces. Figure 7.8 summarizes pertinent information from the test.

Table 7.2. Occupant Risk Factors for Test No. 608331-01-6.

Occupant Risk Factor	Value	Time
OIV		
Longitudinal	24.9 ft/s	at 0.1439 s on left side of interior
Lateral	16.4 ft/s	
Occupant Ridedown Accelerations		
Longitudinal	10.7 g	0.1467 - 0.1567 s
Lateral	9.8 g	0.2125 - 0.2225 s
THIV	8.6 m/s	at 0.1373 s on left side of interior
ASI	1.02	0.2115 - 0.2615 s
Maximum 50-ms Moving Average		
Longitudinal	-9.1 g	0.1163 - 0.1663 s
Lateral	7.7 g	0.1863 - 0.2363 s
Vertical	-4.6 g	0.7919 - 0.8419 s
Maximum Roll, Pitch, and Yaw Angles		
Roll	15°	0.7865 s
Pitch	14°	0.8046 s
Yaw	53°	0.8341 s



General Information

Test Agency..... Texas A&M Transportation Institute (TTI)
 Test Standard Test No. MASH Test 3-21
 TTI Test No. 608331-01-6
 Test Date 2019-12-19

Test Article

Type Transition
 Name 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Installation Length..... 207 ft 3 1/2 inches (incl 154 ft of deck)
 Material or Key Elements ... Thrie beam guardrail terminal to 38-inch tall 2-tube bridge rail, 3/4 inch tall thrie beam guardrail section, symmetrical W-beam to thrie beam terminal, 25 ft of W-beam guardrail
 Soil Type and Condition AASHTO M147 Grading B Soil (crushed limestone), Damp

Test Vehicle

Type/Designation 2270P
 Make and Model 2013 RAM 1500 Pickup
 Curb 4890 lb
 Test Inertial 5038 lb
 Dummy No dummy
 Gross Static 5038 lb

Impact Conditions

Speed 62.6 mi/h
 Angle 24.9°
 Location/Orientation 7.5 ft upstream of post 7

Impact Severity

..... 117 kip-ft
Exit Conditions
 Speed 31.8 mi/h
 Trajectory/Heading Angle... 23.3° / 24.7°

Occupant Risk Values

Longitudinal OIV 24.9 ft/s
 Lateral OIV 16.4 ft/s
 Longitudinal Ridedown 10.7 g
 Lateral Ridedown 9.8 g
 THIV 8.6 m/s
 ASI 1.02
 Max. 0.050-s Average
 Longitudinal -9.1 g
 Lateral 7.7 g
 Vertical -4.6 g

Post-Impact Trajectory

Stopping Distance 133 ft downstream
 2 ft twd traffic

Vehicle Stability

Maximum Yaw Angle 53°
 Maximum Pitch Angle 14°
 Maximum Roll Angle 15°
 Vehicle Snagging No
 Vehicle Pocketing No

Test Article Deflections

Dynamic 33.6 inches
 Permanent 28.0 inches
 Working Width 44.7 inches
 Height of Working Width 61.8 inches

Vehicle Damage

VDS 11LFQ5
 CDC 11FLEW4
 Max. Exterior Deformation 20.0 inches
 OCDI LF000000
 Max. Occupant Compartment Deformation None

Figure 7.8. Summary of Results for MASH Test 3-21 2019 MASH 2-Tube Transition from W-Beam to Thrie Beam.

Chapter 8. SUMMARY AND CONCLUSIONS

8.1 ASSESSMENT OF TEST RESULTS

The crash tests reported herein were performed in accordance with *MASH* TL-3 transitions. An assessment of each test based on the applicable safety evaluation criteria for *MASH* TL-3 transitions is provided in Tables 8.1 through 8.3.

8.2 CONCLUSIONS

Table 8.4 shows the 2019 *MASH* 2-Tube Bridge Rail Thrie Beam Transition performed acceptably as reported herein for a *MASH* TL-3 transition.

Table 8.1. Performance Evaluation Summary for MASH Test 3-20 on 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition.

Test Agency: Texas A&M Transportation Institute

Test No.: 608331-01-4

Test Date: 2019-09-02

MASH Test 3-20 Evaluation Criteria	Test Results	Assessment
<u>Structural Adequacy</u>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition contained and redirected the 1100C vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection was 3.5 inches.	Pass
<u>Occupant Risk</u>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 3.5 inches in the left kick panel area.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 1100C vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 12° and 3°, respectively.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 22.6 ft/s, and lateral OIV was 30.5 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 14.5 g, and lateral occupant ridedown acceleration was 9.2 g.	Pass

Table 8.2. Performance Evaluation Summary for MASH Test 3-21 on 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition from Thrie Beam to Bridge Rail.

Test Agency: Texas A&M Transportation Institute

Test No.: 608331-01-5

Test Date: 2019-09-05

MASH Test 3-21 Evaluation Criteria	Test Results	Assessment
<u>Structural Adequacy</u>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection was 6.1 inches.	Pass
<u>Occupant Risk</u>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 4.0 inches in the left front kick panel.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 8° and 11°, respectively.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 20.3 ft/s, and lateral OIV was 23.6 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 7.4 g, and lateral occupant ridedown acceleration was 13.0 g.	Pass

Table 8.3. Performance Evaluation Summary for MASH Test 3-21 on 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition from W-Beam to Thrie Beam.

Test Agency: Texas A&M Transportation Institute

Test No.: 608331-01-6

Test Date: 2019-12-19

MASH Test 3-21 Evaluation Criteria	Test Results	Assessment
<u>Structural Adequacy</u>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection was 33.6 inches.	Pass
<u>Occupant Risk</u>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	No occupant compartment deformation or intrusion was observed.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 15° and 14°, respectively.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 24.9 ft/s, and lateral OIV was 16.4 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 10.7 g, and lateral occupant ridedown acceleration was 9.8 g.	Pass

Table 8.4. Assessment Summary for MASH TL-3 Testing on 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition.

Evaluation Factors	Evaluation Criteria	Test No. 608331-01-4	Test No. 608331-01-5	Test No. 608331-01-6
Structural Adequacy	A	S	S	S
Occupant Risk	D	S	S	S
	F	S	S	S
	H	S	S	S
	I	S	S	S
MASH Test No.		MASH Test 3-20	MASH Test 3-21 at Transition to Bridge Rail	MASH Test 3-21 at Transition to Thrie Beam
Pass/Fail		Pass	Pass	Pass


Key: S = Satisfactory
 U = Unsatisfactory
 NA = Not applicable

This page intentionally left blank.

REFERENCES




1. C. E. Buth, W. F. Williams, W. L. Menges, and S. K. Schoeneman. *NCHRP Report 350 Test 4-10 of the Alaska Multi-State Bridge Rail*, Test Report No.; 404311-1, Texas A&M Transportation Institute, College Station, TX, December 1998.
2. C. E. Buth, W. F. Williams, W. L. Menges, and S. K. Schoeneman. *NCHRP Report 350 Test 4-11 of the Alaska Multi-State Bridge Rail*, Test Report No.; 404311-2, Texas A&M Transportation Institute, College Station, TX, December 1998.
3. C. E. Buth, W. F. Williams, W. L. Menges, and S. K. Schoeneman. *NCHRP Report 350 Test 4-12 of the Alaska Multi-State Bridge Rail*, Test Report No.; 404311-3, Texas A&M Transportation Institute, College Station, TX, February 1998.
4. C. E. Buth, W. F. Williams, W. L. Menges, and S. K. Schoeneman. *NCHRP Report 350 Test 4-21 of the Alaska Multi-State Bridge Rail Thrie Beam Transition*, Test Report No.; 404311-5, Texas A&M Transportation Institute, College Station, TX, July 1999.
5. C. E. Buth, W. F. Williams, W. L. Menges, and S. K. Schoeneman. *NCHRP Report 350 Test 4-22 of the Alaska Multi-State Bridge Rail Thrie Beam Transition*, Test Report No.; 404311-6, Texas A&M Transportation Institute, College Station, TX, July 1999.
6. C. E. Buth, W. F. Williams, W. L. Menges, and S. K. Schoeneman. *NCHRP Report 350 Test 3-21 of the Alaska Multi-State Bridge Rail W-Beam Transition*, Test Report No.; 404311-7, Texas A&M Transportation Institute, College Station, TX, July 2000.
7. C. E. Buth, W. F. Williams, W. L. Menges, and S. K. Schoeneman. *NCHRP Report 350 Test 3-20 of the Alaska Multi-State Bridge Rail W-Beam Transition*, Test Report No.; 404311-8, Texas A&M Transportation Institute, College Station, TX, August 2000.
8. H. E. Ross, D. L. Sicking, R. A. Zimmer, and J. D. Michie, *Recommended Procedures for the Safety Performance Evaluation of Highway Features*, National Cooperative Highway Research Program Report 350, Transportation Research Board, National Research Council, Washington, D.C., 1993.
9. W. F. Williams, W. L. Menges, and Bill L. Griffith. *MASH TL-4 Evaluation of 2019 MASH 2-Tube Bridge Rail*. Test Report No. 608331-01-1A-2-3. Texas A&M Transportation Institute, College Station, TX, April 2019.
10. AASHTO. *Manual for Assessing Roadside Safety Hardware, Second Edition*. 2016, American Association of State Highway and Transportation Officials: Washington, D.C.
11. AASHTO/FHWA Joint Implementation Agreement for Manual for Assessing Safety Hardware (MASH). https://safety.fhwa.dot.gov/roadway_dept/countermeasures/reduce_crash_severity/docs/memo_joint_implementation_agmt.pdf, January 7, 2016, last access January 2019.

This page intentionally left blank.



C:\Accreditation-17025-2017\EIR-000 Project Files\608331-4-6\608331 4-6 Drawing - Williams\Drafting, 608331 4-5\608331 4-6 Drawing

Transition - Plan




- 2a.** Backfill Post holes with AASHTO M147-65(2004), grade B crushed limestone road base, compacted to MASH standard.
- 2b.** Recessed Guardrail Nuts on all 5/8" Bolts unless otherwise indicated.
- 2c.** All steel components, including hardware, shall be galvanized.


		Roadside Safety and Physical Security Division - Proving Ground	
Project #608331 4-6 Alaska Bridge Transition		2020-03-24	
Drawn by GES	Scale 1:100	Sheet 2 of 13 Transition - Plan	

C:\Accreditation-17025-2017\EIR-000 Project Files\608331 - Alaska - Williams\Drafting, 608331 4-5\608331 4-6 Drawing


Bridge Rail Details




Plan View




Elevation View



Section E-E
Scale 1 : 20
Hardware is x 4 at each Post




Detail F
Scale 1 : 5



Detail G
Scale 1 : 20
Typ each Rail joint (7)
and Deck and Curb joint (2)

		Roadside Safety and Physical Security Division - Proving Ground	
Project #608331 4-6 Alaska Bridge Transition		2020-03-24	
Drawn by GES	Scale 1:250	Sheet 3 of 13 Bridge Rail Details	


Concrete Details, Elevation



- 4a.** Concrete Strength is 5000psi for the Wall and Deck, 3000 psi for the Working Slab, and 4000 psi for the Curb.
- 4b.** Chamfer Field Side edges of Deck, and field side and top edges at end of Curb 3/4" each way as shown.

	Roadside Safety and Physical Security Division - Proving Ground		
	Project #608331 4-6 Alaska Bridge Transition	2020-03-24	
Drawn by GES	Scale 1:250	Sheet 4 of 13 Concrete Details, Elevation	

C:\Accreditation-17025-2017\EIR-000 Project Files\608331- Alaska - Williams\Drafting, 608331 4-5\608331 4-6 Drawing




- 5a.** Place the Anchor Bars @ maximum 18" spacing and secure to existing rebar protruding from the runway with minimum 3" weld. (Existing rebar not shown here.)
- 5b.** Minimum rebar lap is 24" for #4 bars and 30" for #5 bars.
- 5c.** Place one mat of Ø1/2" (#4) bars in Working Slab @ 12" each way with ≈1-1/2" cover at top. These bars are not shown here.
- 5d.** Field bend traffic side longitudinal bar and turn Hoop Bars at ends of Curb to maintain cover.
- 5e.** The Anchor Bars will be bare steel, and the bars in the Working Slab may be bare steel. All other bars shall be epoxy coated, and all bars are grade 60.

Section H-H

Scale 1 : 10


	Roadside Safety and Physical Security Division - Proving Ground	
	Project #608331 4-6 Alaska Bridge Transition	2020-03-24
Drawn by GES	Scale 1:10	Sheet 5 of 13 Rebar Details




- 6a.** Concrete Strength is 5000psi for the Wall and Deck, 3000 psi for the Working Slab, and 4000 psi for the Curb.
- 6b.** Chamfer Field Side edges of Deck, and field side and top edges at end of Curb 3/4" each way as shown.
- 6c.** Rebar placement shown in Detail View at joint is typical each joint. Adjust spacing and Hook Bar direction as needed at location shown.

		Roadside Safety and Physical Security Division - Proving Ground	
Project #608331 4-6 Alaska Bridge Transition		2020-03-24	
Drawn by GES	Scale 1:250	Sheet 6 of 13 Details, Plan	


C:\Accreditation-17025-2017\EIR-000 Project Files\608331 - Alaska - Williams\Drafting, 608331 4-5\608331 4-6 Drawing




		Roadside Safety and Physical Security Division - Proving Ground	
Project #608331 4-6 Alaska Bridge Transition		2020-03-24	
Drawn by GES	Scale 1:10	Sheet 7 of 13 Rebar	




Q:\Accreditation-17025-2017\EIR-000 Project Files\608331- Alaska - Williams\Drafting, 608331 4-5\608331 4-6 Drawing



C:\accreditation-17025-2017\EIR-000 Project Files\608331- Alaska - Williams\Drafting, 608331 4-5\608331 4-6 Drawing






Roadside Safety and Physical Security Division - Proving Ground

Project #608331 4-5 Alaska Bridge Transition		2019-07-03
Drawn by GES	Scale 1:10	Sheet 11 of 13 Guardrail Connection

T:\1-ProjectFiles\608331 - Alaska - Williams\Drafting, 608331 4-5\608331 4-6 Drawing


Transition Angle



12a. Galvanize after fabrication is complete.


		Roadside Safety and Physical Security Division - Proving Ground	
Project #608331 4-6 Alaska Bridge Transition		2020-03-24	
Drawn by GES	Scale 1:5	Sheet 12 of 13 Transition Angle	

Posts and Blockouts




Transition Post
 W6x8.5 x 78"
 ASTM A992 Steel
 (at 9 - 15)

Posts 7 and 8
 W6x8.5 x 72"
 ASTM A992



Long Tubing Blockout
 HSS 12" x 6" x 1/4"
 ASTM A500 Grade B




Short Tubing Blockout
 HSS 12" x 6" x 1/4"
 ASTM A500 Grade B



Roadside Safety and
 Physical Security Division -
 Proving Ground

Project #608331 4-6 Alaska Bridge Transition		2020-03-24
Drawn by GES	Scale 1:10	Sheet 13 of 13 Posts and Blockouts

DISCLOSED INFORMATION IS UNCLASSIFIED UNLESS INDICATED OTHERWISE. THIS DOCUMENT IS UNCLASSIFIED UNLESS INDICATED OTHERWISE. THIS DOCUMENT IS UNCLASSIFIED UNLESS INDICATED OTHERWISE. THIS DOCUMENT IS UNCLASSIFIED UNLESS INDICATED OTHERWISE.



DOWNSTREAM ANCHOR TERMINAL (DAT)
 Only for downstream use, when located outside the horizontal clearance area of opposing traffic.



GENERAL NOTES

1. The detail shown is the minimum Length of Need (LON) for a concrete rail.
2. The rail section at the end post is supported by the Shelf Angle Bracket. The rail element is not attached to the end post.
3. The foundation tubes shall not project more than 3 3/4" above the finished grade.
4. All hardware for DAT shall be ASTM A307 unless otherwise shown.
5. Refer to GF (31) sheet for terminal connection details.

MOW STRIP INSTALLATION

If a mow strip is required with the DAT installation the leave-out area around the steel foundation tubes and the two channel struts may be omitted. This will require a full pour of the foundation tubes.

#	(DAT) PARTS LIST	QTY
1	Steel Foundation Tube	2
2	DAT Terminal Post	2
3	Channel Strut	2
4	Terminal Rail Element	1
5	Shelf Angle Bracket	1
6	BCT Bearing Plate	1
7	BCT Post Sleeve	1
8	Guardrail Anchor Bracket	1
9	(Rounded) W-Beam End Section	1
10	BCT Cable Anchor	1
11	Recessed Nut, Guardrail	20
12	1 1/4" Button Head Bolt	4
13	10" Button Head Bolt	2
14	3/8" x 2" Hex Head Bolt	8
15	3/8" x 8" Hex Head Bolt	4
16	3/8" x 10" Hex Head Bolt	2
17	3/8" Flat Washer	18




Texas Department of Transportation Design Division Standard

METAL BEAM GUARD FENCE (Downstream Anchor Terminal)


GF (31) DAT-14

FILED: gf31dat14.dgn DW: TAD07 DW: AM DW: VP DW: CCL
 DATE: December 2011 DW: SRT JOB: 408894
 REV: 0101
 SHEET NO.




T:\Drafting Department\Solidworks\Standard Parts\Guardrail Parts and Subs\Guardrail Drawings\Post, 72" Wide Flange Guardrail

- NOTES:** 1. ALL FILLETS SHALL HAVE A MINIMUM RADIUS OF 1/16 [2].
 2. IF THE BOLT EXTENDS MORE THAN 1/4 [6] FROM THE NUT THE BOLT SHOULD BE TRIMMED BACK.



DESIGNATOR	L	T (MIN)
FBB01	1-1/4 [32]	1-1/8 [28]
FBB02	2 [51]	1-3/4 [44]
FBB03	10 [254]	4 [102]
FBB04	18 [457]	4 [102]
FBB05	25 [635]	4 [102]



GUARDRAIL BOLT AND RECESSED NUT



FBB01-05

SHEET NO.	DATE:
1 of 2	5/2/2018

SPECIFICATIONS

The geometry and material specifications for this oval shoulder button-headed bolt and hex nut are found in AASHTO M 180. The bolt shall have 5/8-11 [M16x2] threads as defined in ANSI B1.1 [ANSI B1.13M] for Class 2A [6g] tolerances. Bolt material shall conform to ASTM A307 Grade A [ASTM F 568M Class 4.6], with a tensile strength of 60 ksi [400 MPa] and yield strength of 36 ksi [240 MPa]. Material for corrosion-resistant bolts shall conform to ASTM A325 Type 3 [ASTM F 568M Class 8.8.3], with tensile strength of 120 ksi [830 MPa] and yield strength of 92 ksi [660 MPa]. This bolt material has corrosion resistance comparable to ASTM A588 steels. Metric zinc-coated bolt heads shall be marked as specified in ASTM F 568 Section 9 with the symbol “4.6.”

Nuts shall have ANSI B1.1 Class 2B [ANSI B1.13M Class 6h] 5/8-11 [M16x2] threads. The geometry of the nuts, with the exception of the recess shown in the drawing, shall conform to ANSI B18.2.2 [ANSI B18.2.4.1M Style 1] for zinc-coated hex nuts (shown in drawing) and ANSI B18.2.2 [ANSI B18.2.4.6M] for heavy hex corrosion-resistant nuts (not shown in drawing). Material for zinc-coated nuts shall conform to the requirements of AASHTO M 291 (ASTM A 563) Grade A [AASHTO M 291M (ASTM A 563M) Class 5], and material for corrosion-resistant nuts shall conform to the requirements of AASHTO M 291 (ASTM A 563) Grade C3 [AASHTO M 291M (ASTM A 563M) Class 8S3].

When zinc-coated bolts and nuts are required, the coating shall conform to either AASHTO M 232 (ASTM A 153/A 153M) for Class C or AASHTO M 298 (ASTM B 695) for Class 50. Zinc-coated nuts shall be tapped over-size as specified in AASHTO M 291 (ASTM A 563) [AASHTO M 291M (ASTM A 563M)], except that a diametrical allowance of 0.020 inch [0.510 mm] shall be used instead of 0.016 inches [0.420 mm].

Designator	Stress Area of Threaded Bolt Shank (in ² [mm ²])	Min. Bolt Tensile Strength (kips [kN])
FBB01-05	0.226 [157.0]	13.6 [62.8]

Dimensional tolerances not shown or implied are intended to be those consistent with the proper functioning of the part, including its appearance and accepted manufacturing practices.

INTENDED USE


These bolts and nuts are used in numerous guardrail and median barrier designs.

GUARDRAIL BOLT AND RECESSED NUT


FBB01-05		
SHEET NO.	DATE	
2 of 2	5/2/2018	

Thrie-beam End Shoe

10 gauge (0.1345" before galvanizing)



	Roadside Safety and Physical Security Division - Proving Ground	
	Thrie-beam Terminal Connector	2019-07-29
Drawn by GES	Scale 1:5	Sheet 1 of 1



THE CROSS-SECTIONAL DIMENSIONS OF THIS PART ARE THE SAME AS PART RTM01a (SHT 3 of 4)

8-SPACE THRIE-BEAM GUARDRAIL

RTM08a-b

SHEET NO.	DATE:
1 of 2	12/6/2016

SPECIFICATIONS

Corrugated sheet thrie beam guardrail shall conform to the current requirements of AASHTO M180. The section shall be manufactured from sheets with a nominal width of 29½” [750]. RTM08a shall conform to AASHTO M180 Class A and RTM08b shall conform to Class B. Thrie beams may be either Type I or II (zinc-coated) or Type IV (corrosion resistant steel). Corrosion resistant steel should conform to ASTM A606 for Type IV material and shall not be zinc-coated, painted or otherwise treated. Inertial properties are calculated for the whole cross-section without a reduction for the splice bolt holes or slots.

Designator	Area	I _x	I _y	S _x	S _y
	in. ² [10 ³ mm ²]	in. ⁴ [10 ⁶ mm ⁴]	in. ⁴ [10 ⁶ mm ⁴]	in. ³ [10 ³ mm ³]	in. ⁴ [10 ³ mm ³]
RTM08a	3.16 [2.0]	3.8 [1.6]	--	2.22 [36.4]	--
RTM08b	4.03 [2.6]	4.8 [2.0]	--	2.87 [47.0]	--

Dimensional tolerances not shown or implied are intended to be those consistent with the proper functioning of the part, including its appearance and accepted manufacturing practices.

INTENDED USE


The 8-space thrie beam guardrail is used in the W-beam to thrie beam transition with standard posts (STG03a-b).

8-SPACE THRIE-BEAM GUARDRAIL

RTM08a-b

SHEET NO.	DATE:
2 of 2	12/6/2016

DESIGNATOR	BASE METAL THICKNESS
RWT01a	2.67
RTW01b	3.43



THE CROSS-SECTIONAL DIMENSIONS FOR THIS END ARE THE SAME AS PART RTM01a

THE CROSS-SECTIONAL DIMENSIONS FOR THIS END ARE THE SAME AS PART RWB01a-b

1994

W-THRIE BEAM TRANSITION SECTION

RWT01a-b

SHEET NO.	REF. NO.
1 of 2	RE-69-76

1

2

3



DESIGNATOR	BASE METAL THICKNESS
RWM04a	2.67
RWM04b	3.43

4 EQUAL POST HOLE SPACINGS @ 952.5 EA

216

108

952.5 (TYP)



24x30 SPLICE BOLT SLOTS (TYP)
20x65 POST BOLT SLOT (TYP)

4130

THE CROSS-SECTIONAL DIMENSIONS OF THIS PART ARE THE SAME AS PART RWM02a (SHT 3 of 4).

1994

4-SPACE W-BEAM GUARDRAIL



RWM04a-b

SHEET NO.	REF. NO.
1 of 2	RE-3-73

SPECIFICATIONS

Corrugated sheet steel beams shall conform to the current requirements of AASHTO M180. The section shall be manufactured from sheets with a nominal width of 483 mm. Guardrail RWM04a shall conform to AASHTO M180 Class A and RWM04b shall conform to Class B. Corrosion protection may be either Type II (zinc-coated) or Type IV (corrosion resistant steel). Corrosion resistant steel should conform to ASTM A606 for Type IV material and shall not be zinc-coated, painted or otherwise treated. Inertial properties are calculated for the whole cross-section without a reduction for the splice bolt holes.

Designator	Area (10 ³ mm ²)	I _x (10 ⁶ mm ⁴)	I _y (10 ⁶ mm ⁴)	S _x (10 ³ mm ³)	S _y (10 ³ mm ³)
RWM04a-b	1.3	1.0	--	23	--

Dimensional tolerances not shown or implied are intended to be those consistent with the proper functioning of the part, including its appearance and accepted manufacturing practices.

INTENDED USE


This corrugated sheet steel beam is used as a rail element in transition systems STB02 and STB03 or when a reduced post spacing is desired in the SGR02, SGR04a-b, SGM02, and SGM04a-b.

4-SPACE W-BEAM GUARDRAIL

RWM04a-b

SHEET NO.	DATE
2 of 2	04-01-95






1994


RECTANGULAR GUARDRAIL PLATE WASHER

FWR03


SHEET NO.	REF. NO.
1 of 2	F-12-73




PLAN (a)



PLAN (b)



SIDE



FRONT

1994

W-BEAM TIMBER BLOCKOUT

PDB01a-b

SHEET NO.	DATE:
1 of 2	6/30/2005

SPECIFICATIONS

Blockouts shall be made of timber with a stress grade of at least 1160 psi [8 MPa]. Grading shall be in accordance with the rules of the West Coast Lumber Inspection Bureau, Southern Pine Inspection Bureau, or other appropriate timber association. Timber for blockouts shall be either rough-sawn (unplaned) or S4S (surfaced four sides) with nominal dimensions indicated. The variation in size of blockouts in the direction parallel to the axis of the bolt holes shall not be more than $\pm \frac{1}{4}$ inch [6 mm]. Only one type of surface finish shall be used for posts and blockouts in any one continuous length of guardrail.

All timber shall receive a preservation treatment in accordance with AASHTO M 133 after all end cuts are made and holes are drilled.

Dimensional tolerances not shown or implied are intended to be those consistent with the proper functioning of the part, including its appearance and accepted manufacturing practices.

INTENDED USE

Blockout PDB01a is used with wood post PDE01 or PDE02 in the SGR04b strong-post W-beam guardrail and the SGM04b median barrier. Blockout PDB01b is routed to be used with steel post PWE01 or PWE02 in the SGR04c guardrail and the SGM04a median barrier.

W-BEAM TIMBER BLOCKOUT

PDB01a-b

PDB01a-b		
SHEET NO.	DATE	
2 of 2	7/06/2005	

APPENDIX B. SUPPORTING CERTIFICATION DOCUMENTS

PLATE A36 TEMPER LEVELED
1/2 X 48.0000" X 96.0000"

PO/REL HOU-35377/
HEAT: J75904

BL HOU-775673-8 6/21/2019
Order HOU-251290-9 Page:1



CERTIFICATE OF ANALYSIS

Cert Number 38789-5 6/18/2019
Test Reference 52133

TRIPLE-S STEEL SUPPLY CO.
6000 JENSEN DRIVE
HOUSTON, TX 77026

Issued from
BESHERT STEEL PROCESSING
JOINT VENTURE OF
STEEL WAREHOUSE CO. &
TRIPLE-S STEEL HOLDINGS INC.
15355 JACINTO PORT BOULEVARD
HOUSTON, TX 77015

Sold To: TRIPLE-S STEEL SUPPLY CO., 6000 JENSEN DRIVE, HOUSTON, TX 77026
Ship To: TRIPLE-S STEEL, 6000 JENSEN DRIVE, HOUSTON, TX 77026

Customer 100200/0 Your Order HOU-185586 (6/12/2019)
Our Order 19485-1-1 Packing List 38789-1 (6/18/2019)

Reference
HOU-185586 (6/12/2019)
38789-1 (6/18/2019)

TEMPERED LEVELED PLATE A36/SA36
0.5000" x 48" x 96"

Product Information
Heat J75904

Tag	Pcs	LBS
23666C	15	9,805
23666O	15	9,805
23666E	15	9,805
23666F	10	6,536
	55	35,951

Part PL36TML1248
Conform To ASTM-A36-.312-.750 4/27/2013

Chemical Composition

C.E.: 0.1935 D.I.: 0

C	Mn	Si	P	S	Cr	Ni	Mo
0.0466	0.80	0.022	0.013	0.0031	0.02	0.04	0.01
Cu	Al	V	Ti	Cb	CbV		
0.07	0.016	0.001	0.001	0.013	0.014		

Physical Tests

YIELD - H (T)	TENSILE - H (T)	ELONGATION - H (T)	YIELD - M (T)
55.7 KSI	63.2 KSI	34.5 %	56.7 KSI
TENSILE - M (T)	ELONGATION - M (T)		
62.6 KSI	34.5 %		

Product of Coil
Country of Origin: Korea

608331

6/18/2019 09:33 AM 1

검사증명서 MILL TEST CERTIFICATE

**HYUNDAI
STEEL**

당진제철소 : 오남 당진시 송악읍 북부산업로 1460
1460 Bukbuseup-Ro, Songae-Eup, Dangjin-Si, Chungnam, Korea



주문번호
Order No. : E190200039

품명
Commodity : Hot Rolled Coil

제품규격
Specification : ASTM A 36

고객사
Customer : Boshen Steel

주요자
Contractor : SKC

증명서 번호
Certificate No. : 20190324-HS-013-010

발행 일자
Date of Issue : 2019-03-24

제품차수 Dimension (inch)	수량 Quantity	중량 Weight (kg)	재질번호 Heat No.	제품번호 Product No.	POSITION	인장시험 Tensile Test						화학성분 Chemical Composition(%)										단위 mm 2: x100 3: x1,000 4: x10,000 5: x100,000				
						YP	TS	EL	YP-EL	RA	YR	YP	YS	C	Si	Mn	P	S	Cr	Ni	Cu	Mo	Nb	Ti	V	Su -AI
						(kgf/cm ²)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)	(%)
0.50831NOM x 48" x C	1	21,460	J75902	HC30953	B	303.0	449.9	41				2	L	446	26	920	120	24	2	3	70	1	12	1	2	25
0.50831NOM x 48" x C	1	21,640	J75902	HC30654	B	350.9	449.9	41				2	L	446	26	920	120	24	2	3	70	1	12	1	2	25
0.50831NOM x 48" x C	1	21,450	J75902	HC30655	B	344.8	446.0	42				2	L	446	26	920	120	24	2	3	70	1	12	1	2	25
0.50831NOM x 48" x C	1	21,490	J75904	HC30573	B	344.1	444.2	42				2	L	455	22	800	130	31	2	4	70	1	13	1	1	16
0.50831NOM x 48" x C	1	21,880	J75904	HC30574	B	344.1	444.2	42				2	L	455	22	800	130	31	2	4	70	1	13	1	1	16
*** Sub Total(016) ***						5	107,710(kg)																			

NOTE
 - Position - T:Top, M:Middle, B:Bottom
 - Tensile test - Direction:Transverse, Gauge length:50mm (Rectangular), YP Mid : 2 (0.2% off-set), 5 (0.5% underload), U (Upper yield point), L (Lower yield point)
 - Division - P:Product analysis, L:Ladle analysis

실기의 제품은 전사에 걸쳐 자정된 규격에 합격한 것을 증명합니다.
 WE HEREBY CERTIFY THAT THE MATERIAL HAS BEEN MADE AND TESTED IN ACCORDANCE WITH THE ABOVE SPECIFICATION AND THE REQUIREMENTS

Signature
S. B. Park
 Chief Of Quality Assurance Team

* 본 검사증명서는 원문만 전자문서(전자서명 또는 동등)로만 유효하며 사본입니다. 전자문서의 내용은 원문과 동일함을 증명할 수 있습니다. (http://www.hyundai-steel.com/cv/vopgh.jsp)
 * This Mill Test Certificate is a copy that has been printed from original electronic document (with digital signed). You are able to check an original electronic document at Hyundai's customer portal (http://www.hyundai-steel.com/cv/vopgh.jsp) * QRcode scanner App : "QRfast"
 * [제품용 주의사항] 본 검사증명서를 열거한 규격 외 사용자 제품모양 및 안전성 문제가 발생될 수 있습니다.
 * [Caution for Use] Damage on products and safety problems may arise if used other than to the spec stated in this Mill Test Certification.

PLATE A36 TEMPER LEVELLED
 1/2 X 48.000" X 96.000"
 Our Order 19403-1-1 Your Order MNU-150000
 PO:REL-HOU-35377/
 HEAT: J75904
 BL: HOU-775673-8 6/21/2019
 Order HOU-251290-9 Page:2

RECTANGULAR TUBING A500 GR B
12 X 6 X .250 X 20'

PO/REL HOU-35377/
HEAT: A8U3188

BL HOU-775673-9 6/21/2019
Order HOU-251290-10 Page:1

Southland Tube
a Nucor Company

3525 Richard Arrington Jr Blvd N
Birmingham, AL 35234
800-543-9024
Fax: 205-251-1553

<https://www.nucortubular.com>
<https://www.ntportal.com>
Certificate Number: BHM 950476

Sold By:
SOUTHLAND TUBE INCORPORATED
3525 Richard Arrington Jr Blvd N
Birmingham, AL 35234
Tel: 800-543-9024
Fax: 205-251-1553

Purchase Order No: HOU-183284
Sales Order No: BHM 494279 - 4
Bill of Lading No: BHM 3197 - 3
Invoice No:

Shipped: 1/4/2019
Invoiced:

Shipped To:
2039 - TRIPLE "S" STEEL SUPPLY
P.O. BOX 21119
HOUSTON, TX 77226

Ship To:
8 - IRVINGTON WAREHOUSE
8411 IRVINGTON
HOUSTON, TX 77022

CERTIFICATE of ANALYSIS and TESTS

Customer Part No:

Certificate No: BHM 950476

TUBING A500 GRADE B(C)
12" X 6" X 1/4" X 40'

Test Date: 1/3/2019

Total Pieces 18 Total Weight 21,045

Bundle Tag	Mill	Heat	Specs	Y/T Ratio	Pieces	Weight
415341	6N	A8U3188	YLD=65284/TEN=80606/ELG=29.5/RWB=84.4	0.8099	6	7,015
719919	78	1815098	YLD=56200/TEN=75300/ELG=31/RWB=83.37	0.7463	6	7,015
731578	78N	1815097	YLD=61000/TEN=76800/ELG=32.5/RWB=84.89	0.7943	6	7,015

Mill #: 78N Heat #: 1815097 Carbon Eq: 0.3766 Heat Src Origin: MELTED AND MANUFACTURED IN THE USA

C	Mn	P	S	Si	Al	Cu	Cr	Mo	V	Ni	Sn	N
0.2200	0.8400	0.0050	0.0010	0.0300	0.0280	0.0900	0.0300	0.0100	0.0030	0.0300	0.0050	0.0050
Ti	Ca											
0.0010	0.0020											

LEED Information (based on the most recent LEED information from the producing mill)

Method	Location	Recycled Content	Post Consumer	Post Industrial
EAF	Berkeley, SC	40.0%	29.8%	10.2%

Mill #: 78 Heat #: 1815098 Carbon Eq: 0.3621 Heat Src Origin: MELTED AND MANUFACTURED IN THE USA

C	Mn	P	S	Si	Al	Cu	Cr	Mo	V	Ni	Sn	N
0.2100	0.8200	0.0050	0.0030	0.0300	0.0260	0.0700	0.0300	0.0100	0.0040	0.0300	0.0050	0.0060
Ti	Ca											
0.0010	0.0030											

LEED Information (based on the most recent LEED information from the producing mill)

Method	Location	Recycled Content	Post Consumer	Post Industrial
EAF	Berkeley, SC	40.0%	29.8%	10.2%

Mill #: 6N Heat #: A8U3188 Carbon Eq: 0.3995 Heat Src Origin: MELTED AND MANUFACTURED IN THE USA

C	MN	P	S	Si	Cu	Sn	Ni	Cr	Mo	Al	N	V
0.2200	0.9000	0.0090	0.0060	0.0400	0.1500	0.0000	0.0500	0.0600	0.0160	0.0240	0.0060	0.0050
Cb	Ti	B	Ca	Ce								
0.0030	0.0020	0.0002	0.0014	0.3995								

LEED Information (based on the most recent LEED information from the producing mill)

Method	Location	Recycled Content	Post Consumer	Post Industrial
EAF	Tuscaloosa, AL	56.6%	31.6%	25.0%

RECTANGULAR TUBING A500 GR B
12 X 6 X .250 X 20'

PO/REL HOU-35377/
HEAT: A8U3188

BL HOU-775673-9 6/21/2019
Order HOU-251290-10 Page:2

Southland Tube
a Nucor Company

3525 Richard Arrington Jr Blvd N
Birmingham, AL 35234
800-543-9024
Fax: 205-251-1553

<https://www.nucortubular.com>
<https://www.ntportal.com>
Certificate Number: BHM 950476

Certification:

I certify that the above results are a true and correct copy of records prepared and maintained by Southland Tube Incorporated.
Sworn this day, 1/3/2019.

WE PROUDLY MANUFACTURE ALL OUR PRODUCTS IN THE USA
NUCOR TUBULAR PRODUCTS ARE MANUFACTURED, TESTED,
AND INSPECTED IN ACCORDANCE WITH ASTM STANDARDS.
MATERIAL IDENTIFIED AS A500 GRADE B(C) MEETS BOTH
ASTM A500 GRADE B AND A500 GRADE C SPECIFICATIONS.

CURRENT STANDARDS:

A252-10
A500/A500M-18
A513/A513M-15
ASTM A53/A53M-12 | ASME SA-53/SA-53M-13
A847/A847M-14
A1085/A1085M-15



Barney Hatten
Supervisor of Technical Services & Quality Standards



-ML-JACKSON TN
1 GERDAU AMERISTEEL ROAD
CKSON, TN 38305

BL HOU-775673-10 07/21/2019
Order HOU-251290-11 Page:1

PO/REL HOU-35377/
HEAT: 63191654

FLAT BAR A-36/V 529 GR50
1/2 X 4 X 20

CERTIFIED MATERIAL TEST REPORT

Page 1/1

CUSTOMER SHIP TO TRIPLE S STEEL SUPPLY 6000 JENSEN DR HOUSTON, TX 77026-1113 USA		CUSTOMER BILL TO TRIPLE S STEEL 6000 JENSEN DR HOUSTON, TX 77226-1119 USA		GRADE GGMULTI	SHAPE / SIZE Flat Bar / 1/2 X 4	DOCUMENT ID: 0000222766
SALES ORDER 7834148/000050		CUSTOMER MATERIAL N°		LENGTH 20'00"	WEIGHT 39,168 LB	HEAT / BATCH 63191654/02
CUSTOMER PURCHASE ORDER NUMBER DU-185454		BILL OF LADING 1333-0000129880	DATE 06/08/2019	SPECIFICATION / DATE of REVISION ASTM A529-14, A572-15 ASTM A6-17, A36-14, ASME SA-36 ASTM A709-17, AASHTO M270-15 CSA G40.20-13/G40.21-13		

CHEMICAL COMPOSITION													
C %	Mn %	P %	S %	Si %	Cu %	Ni %	Cr %	Mo %	V %	Nb %	Al %	CEq	A529
0.16	0.75	0.019	0.025	0.21	0.34	0.11	0.16	0.034	0.004	0.008	0.002		0.39

MECHANICAL PROPERTIES													
Elong. %	G/L Inch	G/L mm	UTS PSI	UTS MPa	YS PSI	YS MPa							
25.00	8.000	200.0	78067	538	56337	56579							
23.00	8.000	200.0	77750	536									

METROLOGICAL CHARACTERISTICS													
R:R													
17.38													

COMMENTS / NOTES

is grade meets the requirements for the following grades:
 TM Grades: A36; A529-50; A572-50; A709-36; A709-50
 A Grades: 44W; 50W
 SHTO Grades: M270-36; M270-50
 ME Grades: SA36

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

Bhaskar
 BHASKAR YALAMANCHILI
 QUALITY DIRECTOR







Phone: (+09) 267-1071 Email: Bhaskar.Yalamanchili@gerdau.com

Ben Lovell
 BEN LOVELL
 QUALITY ASSURANCE MGR.

Phone: (731) 423-5213 Email: benjamin.lovell@gerdau.com


This page intentionally left blank.

Table C.1. Summary of Strong Soil Test Results for Establishing Installation Procedure.

 <p>Dynamic Setup</p> <p>Post-Test Photo of post</p>	 <p>Post-Test Photo</p> <p>Static Load Test</p>
<p>Percent Finer Vs. Grain Size of Fill Soil for Dynamic and Static Load Tests</p> 	 <p>Dynamic Test Installation Details</p>
<p>Comparison of Load vs. Displacement at 25-inch height</p> 	 <p>Static Load Test Installation Details</p>

Date	2008-11-05
Test Facility and Site Location	TTI Proving Ground, 3100 SH 47, Bryan, TX 77807
In Situ Soil Description (ASTM D2487)	Sandy gravel with silty fines
Fill Material Description (ASTM D2487) and sieve analysis	AASHTO Grade B Soil-Aggregate (see sieve analysis above)
Description of Fill Placement Procedure	6-inch lifts tamped with a pneumatic compactor
Bogie Weight	5009 lb
Impact Velocity	20.5 mph

Table C.2. Test Day Static Soil Strength Documentation for Test No. 608331-01-4.



Date..... 2019-09-02


Test Facility and Site Location TTI Proving Ground – 3100 SH 47, Bryan, Tx

In Situ Soil Description (ASTM D2487) Sandy gravel with silty fines

Fill Material Description (ASTM D2487) and sieve analysis .. AASHTO Grade B Soil-Aggregate (see sieve analysis)


Description of Fill Placement Procedure 6-inch lifts tamped with a pneumatic compactor

Table C.3. Test Day Static Soil Strength Documentation for Test No. 608331-01-5.



Date.....	<u>2019-09-05</u>
Test Facility and Site Location	<u>TTI Proving Ground – 3100 SH 47, Bryan, Tx</u>
In Situ Soil Description (ASTM D2487)	<u>Sandy gravel with silty fines</u>
Fill Material Description (ASTM D2487) and sieve analysis ..	<u>AASHTO Grade B Soil-Aggregate (see sieve analysis)</u>
Description of Fill Placement Procedure	<u>6-inch lifts tamped with a pneumatic compactor</u>

Table C.4. Test Day Static Soil Strength Documentation for Test No. 608331-01-6.



Typical Static Load Setup



Post-Test Photo of Post

Date.....	<u>2019-12-19</u>
Test Facility and Site Location	<u>TTI Proving Ground – 3100 SH 47, Bryan, Tx</u>
In Situ Soil Description (ASTM D2487)	<u>Sandy gravel with silty fines</u>
Fill Material Description (ASTM D2487) and sieve analysis ..	<u>AASHTO Grade B Soil-Aggregate (see sieve analysis)</u>
Description of Fill Placement Procedure	<u>6-inch lifts tamped with a pneumatic compactor</u>

APPENDIX D. MASH TEST 3-20 (CRASH TEST NO. 608331-01-4)

D1 VEHICLE PROPERTIES AND INFORMATION

Table D.1. Vehicle Properties for Test No. 608331-01-4.

Date: 2019-09-02 Test No.: 608331-4 VIN No.: KNADE123376251020

Year: 2007 Make: Kia Model: Rio

Tire Inflation Pressure: 32 PSI Odometer: 137463 Tire Size: 185/65R14

Describe any damage to the vehicle prior to test: None

• Denotes accelerometer location.

NOTES: None

Engine Type: 4 CYL

Engine CID: 1.6 L

Transmission Type:

Auto or Manual
 FWD RWD 4WD



Optional Equipment:
None

Dummy Data:

Type: 50th Percentile Male

Mass: 165 lb

Seat Position: IMPACT SIDE



Geometry: inches

A <u>66.38</u>	F <u>33.00</u>	K <u>12.25</u>	P <u>4.12</u>	U <u>14.75</u>
B <u>51.50</u>	G <u> </u>	L <u>25.25</u>	Q <u>22.50</u>	V <u>20.50</u>
C <u>165.75</u>	H <u>35.04</u>	M <u>57.75</u>	R <u>15.50</u>	W <u>35.00</u>
D <u>34.00</u>	I <u>7.75</u>	N <u>57.70</u>	S <u>8.25</u>	X <u>72.50</u>
E <u>98.75</u>	J <u>21.50</u>	O <u>27.00</u>	T <u>66.20</u>	
Wheel Center Ht Front <u>11.00</u>		Wheel Center Ht Rear <u>11.00</u>		W-H <u>0.00</u>

RANGE LIMIT: A = 65 ±3 inches; C = 169 ±8 inches; E = 98 ±5 inches; F = 35 ±4 inches; H = 39 ±4 inches; O (Bottom of Hood Lip) = 24 ±4 inches
 TOP OF RADIATOR SUPPORT = 28.25 inches; (M+N)/2 = 56 ±2 inches; W-H < 2 inches or use MASH Paragraph A4.3.2

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front <u>1718</u>	M _{front}	<u>1602</u>	<u>1578</u>	<u>1663</u>
Back <u>1874</u>	M _{rear}	<u>868</u>	<u>868</u>	<u>948</u>
Total <u>3638</u>	M _{Total}	<u>2470</u>	<u>2446</u>	<u>2611</u>




Allowable TIM = 2420 lb ±55 lb | Allowable GSM = 2585 lb ± 55 lb

Mass Distribution:

lb LF: 766 RF: 812 LR: 452 RR: 416

Table D.3. Occupant Compartment Measurements for Test No. 608331-01-4.

Date: 2019-09-02 Test No.: 608331-4 VIN No.: KNADE123376251020
 Year: 2007 Make: Kia Model: Rio



OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT

	Before	After (inches)	Differ.
A1	67.50	67.50	0.00
A2	67.25	67.25	0.00
A3	67.75	67.75	0.00
B1	40.50	40.50	0.00
B2	39.00	39.00	0.00
B3	40.50	40.50	0.00
B4	36.25	36.25	0.00
B5	36.00	36.00	0.00
B6	36.25	36.25	0.00
C1	26.00	23.00	-3.00
C2	0.00	0.00	0.00
C3	26.00	26.00	0.00
D1	9.50	11.50	2.00
D2	0.00	0.00	0.00
D3	9.50	9.50	0.00
E1	51.50	53.00	1.50
E2	51.00	55.50	4.50
F	51.00	51.00	0.00
G	51.00	51.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	51.00	47.50	-3.50

*Lateral area across the cab from driver's side kick panel to passenger's side kick panel.

D2 SEQUENTIAL PHOTOGRAPHS



0.000 s



0.100 s



0.200 s



0.300 s



Figure D.1. Sequential Photographs for Test No. 608331-01-4 (Overhead and Frontal Views).



0.400 s



0.500 s



0.600 s



0.700 s



Figure D.1. Sequential Photographs for Test No. 608331-01-4 (Overhead and Frontal Views) (Continued).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s




0.300 s



0.700 s

Figure D.2. Sequential Photographs for Test No. 608331-01-4 (Rear View).


Roll, Pitch, and Yaw Angles



— Roll — Pitch — Yaw


Axes are vehicle-fixed.
Sequence for determining orientation:

1. Yaw.
2. Pitch.
3. Roll.



Test Number: 608331-01-4
 Test Standard Test Number: MASH Test 3-20
 Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Test Vehicle: 2007 Kia Rio
 Inertial Mass: 2446 lb
 Gross Mass: 2611 lb
 Impact Speed: 60.9
 Impact Angle: 26.5°

Figure D.3. Vehicle Angular Displacements for Test No. 608331-01-4.




— Time of OIV (0.0824 sec) — SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-4
Test Standard Test Number: MASH Test 3-20
Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
Test Vehicle: 2007 Kia Rio
Inertial Mass: 2446 lb
Gross Mass: 2611 lb
Impact Speed: 60.9
Impact Angle: 26.5°

**Figure D.4. Vehicle Longitudinal Accelerometer Trace for Test No. 608331-01-4
(Accelerometer Located at Center of Gravity).**

Y Acceleration at CG




— Time of OIV (0.0824 sec) — SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-4
Test Standard Test Number: MASH Test 3-20
Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
Test Vehicle: 2007 Kia Rio
Inertial Mass: 2446 lb
Gross Mass: 2611 lb
Impact Speed: 60.9
Impact Angle: 26.5°

**Figure D.5. Vehicle Lateral Accelerometer Trace for Test No. 608331-01-4
(Accelerometer Located at Center of Gravity).**

Z Acceleration at CG



— SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-4
 Test Standard Test Number: MASH Test 3-20
 Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Test Vehicle: 2007 Kia Rio
 Inertial Mass: 2446 lb
 Gross Mass: 2611 lb
 Impact Speed: 60.9
 Impact Angle: 26.5°

**Figure D.6. Vehicle Vertical Accelerometer Trace for Test No. 608331-01-4
 (Accelerometer Located at Center of Gravity).**

APPENDIX E. MASH TEST 3-21 (CRASH TEST NO. 608331-01-5)

E1 VEHICLE PROPERTIES AND INFORMATION

Table E.1. Vehicle Properties for Test No. 608331-01-5.

Date: 2019-09-05 Test No.: 608331-5 VIN No.: 1C6RR6HTODS501020
 Year: 2013 Make: RAM Model: 1500
 Tire Size: 265/70 R 17 Tire Inflation Pressure: 35 psi
 Tread Type: Highway Odometer: 152402
 Note any damage to the vehicle prior to test: None

• Denotes accelerometer location.


NOTES: None

Engine Type: V-8
 Engine CID: 4.7 liter

Transmission Type:
 Auto or Manual
 FWD RWD 4WD

Optional Equipment:
None

Dummy Data:
 Type: 50th percentile male
 Mass: 165 lb
 Seat Position: IMPACT SIDE



Geometry: inches

A	78.50	F	40.00	K	20.00	P	3.00	U	26.75
B	74.00	G	28.25	L	30.00	Q	30.50	V	30.25
C	227.50	H	60.84	M	68.50	R	18.00	W	60.80
D	44.00	I	11.75	N	68.00	S	13.00	X	79.00
E	140.50	J	27.00	O	46.00	T	77.00		
Wheel Center Height Front	14.75	Wheel Well Clearance (Front)	6.00	Bottom Frame Height - Front	12.50				
Wheel Center Height Rear	14.75	Wheel Well Clearance (Rear)	9.25	Bottom Frame Height - Rear	22.50				

RANGE LIMIT: A=78 ±2 inches; C=237 ±13 inches; E=148 ±12 inches; F=39 ±3 inches; G = > 28 inches; H = 63 ±4 inches; O=43 ±4 inches; (M+N)/2=67 ±1.5 inches

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front	3700	M _{front}	2962	2948
Back	3900	M _{rear}	2206	2267
Total	6700	M _{Total}	5168	5215

(Allowable Range for TIM and GSM = 5000 lb ±110 lb)

Mass Distribution:
 lb LF: 1475 RF: 1388 LR: 1070 RR: 1117

Table E.2. Measurements of Vehicle Vertical CG for Test No. 608331-01-5.

Date: 2019-09-05 Test No.: 608331-5 VIN: 1C6RR6HTODS501020
 Year: 2013 Make: RAM Model: 1500
 Body Style: Quad Cab Mileage: 152402
 Engine: 4.7 liter V-8 Transmission: Automatic
 Fuel Level: Empty Ballast: 100 (440 lb max)
 Tire Pressure: Front: 35 psi Rear: 35 psi Size: 265/70 R 17

Measured Vehicle Weights: (lb)							
LF:	1475		RF:	1388		Front Axle:	2863
LR:	1070		RR:	1117		Rear Axle:	2187
Left:	2545		Right:	2505		Total:	5050
							5000 ±110 lb allowed
Wheel Base:	140.50	inches	Track: F:	68.50	inches	R:	68.00 inches
148 ±12 inches allowed			Track = (F+R)/2 = 67 ±1.5 inches allowed				
Center of Gravity, SAE J874 Suspension Method							
X:	60.85	inches	Rear of Front Axle	(63 ±4 inches allowed)			
Y:	-0.27	inches	Left -	Right +	of Vehicle Centerline		
Z:	28.25	inches	Above Ground	(minimum 28.0 inches allowed)			

Hood Height: 46.00 inches Front Bumper Height: 27.00 inches
 43 ±4 inches allowed

Front Overhang: 40.00 inches Rear Bumper Height: 30.00 inches
 39 ±3 inches allowed

Overall Length: 227.50 inches
 237 ±13 inches allowed

Table E.3. Exterior Crush Measurements for Test No. 608331-01-5.

Date: 2019-09-05 Test No.: 608331-5 VIN No.: 1C6RR6HTODS501020
 Year: 2013 Make: RAM Model: 1500

VEHICLE CRUSH MEASUREMENT SHEET¹

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____	Bowing: B1 _____ X1 _____
Corner shift: A1 _____	B2 _____ X2 _____
A2 _____	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} =$ _____
< 4 inches _____	
≥ 4 inches _____	

Note: Measure C₁ to C₆ from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L***	C ₁	C ₂	C ₃	C ₄	C ₅	C ₆	±D
		Width** (CDC)	Max**** Crush								
1	Front plane at bumper ht	22	14	28	14	9.5	5	3	1	0	-12
2	Side plane at bumper ht	22	15	62	15	11	-	-	8	8	+75
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

¹Table taken from National Accident Sampling System (NASS).

*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.

**Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).




***Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

Table E.4. Occupant Compartment Measurements for Test No. 608331-01-5.

Date: 2019-09-05 Test No.: 608331-5 VIN No.: 1C6RR6HTODS501020
 Year: 2013 Make: RAM Model: 1500

OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT



	Before	After (inches)	Differ.
A1	65.00	65.00	0.00
A2	63.00	63.00	0.00
A3	65.50	65.50	0.00
B1	45.00	45.00	0.00
B2	38.00	38.00	0.00
B3	45.00	45.00	0.00
B4	39.50	39.50	0.00
B5	43.00	43.00	0.00
B6	39.50	39.50	0.00
C1	26.00	25.00	-1.00
C2	0.00	0.00	0.00
C3	26.00	26.00	0.00
D1	11.00	10.00	-1.00
D2	0.00	0.00	0.00
D3	11.50	11.50	0.00
E1	58.50	60.50	2.00
E2	63.50	67.50	4.00
E3	63.50	63.50	0.00
E4	63.50	63.50	0.00
F	59.00	59.00	0.00
G	59.00	59.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	25.00	21.00	-4.00

*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.

E2 SEQUENTIAL PHOTOGRAPHS



0.000 s



0.100 s



0.200 s



0.300 s



Figure E.1. Sequential Photographs for Test No. 608331-01-5 (Overhead and Frontal Views).



0.400 s



0.500 s



0.600 s



0.700 s



Figure E.1. Sequential Photographs for Test No. 608331-01-5 (Overhead and Frontal Views) (Continued).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s




0.300 s



0.700 s

Figure E.2. Sequential Photographs for Test No. 608331-01-5 (Rear View).


Roll, Pitch, and Yaw Angles



— Roll — Pitch — Yaw


Axes are vehicle-fixed.
Sequence for determining orientation:

1. Yaw.
2. Pitch.
3. Roll.



Test Number: 608331-01-5
 Test Standard Test Number: MASH Test 3-21
 Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Test Vehicle: 2013 RAM 1500 Pickup
 Inertial Mass: 5050 lb
 Gross Mass: 5215 lb
 Impact Speed: 61.9 mi/h
 Impact Angle: 25.3°

Figure E.3. Vehicle Angular Displacements for Test No. 608331-01-5.




— Time of OIV (0.1075 sec) — SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-5
Test Standard Test Number: MASH Test 3-21
Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
Test Vehicle: 2013 RAM 1500 Pickup
Inertial Mass: 5050 lb
Gross Mass: 5215 lb
Impact Speed: 61.9 mi/h
Impact Angle: 25.3°

**Figure E.4. Vehicle Longitudinal Accelerometer Trace for Test No. 608331-01-5
(Accelerometer Located at Center of Gravity).**

Y Acceleration at CG




— Time of OIV (0.1075 sec) — SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-5
 Test Standard Test Number: MASH Test 3-21
 Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Test Vehicle: 2013 RAM 1500 Pickup
 Inertial Mass: 5050 lb
 Gross Mass: 5215 lb
 Impact Speed: 61.9 mi/h
 Impact Angle: 25.3°

Figure E.5. Vehicle Lateral Accelerometer Trace for Test No. 608331-01-5 (Accelerometer Located at Center of Gravity).

Z Acceleration at CG



— SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-5
 Test Standard Test Number: MASH Test 3-21
 Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Test Vehicle: 2013 RAM 1500 Pickup
 Inertial Mass: 5050 lb
 Gross Mass: 5215 lb
 Impact Speed: 61.9 mi/h
 Impact Angle: 25.3°

**Figure E.6. Vehicle Vertical Accelerometer Trace for Test No. 608331-01-5
 (Accelerometer Located at Center of Gravity).**

This page intentionally left blank.

APPENDIX F. MASH TEST 3-21 (CRASH TEST NO. 608331-01-6)

F1 VEHICLE PROPERTIES AND INFORMATION

Table F.1. Vehicle Properties for Test No. 608331-01-6.

Date: 2019-12-19 Test No.: 608331-6 VIN No.: 1C6RR6FT8DS724487
 Year: 2013 Make: RAM Model: 1500
 Tire Size: 265/70 R 17 Tire Inflation Pressure: 35 psi
 Tread Type: Highway Odometer: 144145
 Note any damage to the vehicle prior to test: None

• Denotes accelerometer location.

NOTES: None

Engine Type: V-8
 Engine CID: 4.7 liter

Transmission Type:
 Auto or Manual
 FWD RWD 4WD

Optional Equipment:
None

Dummy Data:
 Type: No dummy used
 Mass: 0 lb
 Seat Position: _____

Geometry: inches

A	<u>78.50</u>	F	<u>40.00</u>	K	<u>20.00</u>	P	<u>3.00</u>	U	<u>26.75</u>
B	<u>74.00</u>	G	<u>29.00</u>	L	<u>30.00</u>	Q	<u>30.50</u>	V	<u>30.25</u>
C	<u>227.50</u>	H	<u>61.52</u>	M	<u>68.50</u>	R	<u>18.00</u>	W	<u>61.50</u>
D	<u>44.00</u>	I	<u>11.75</u>	N	<u>68.00</u>	S	<u>13.00</u>	X	<u>79.00</u>
E	<u>140.50</u>	J	<u>27.00</u>	O	<u>46.00</u>	T	<u>77.00</u>		
Wheel Center Height Front	<u>14.75</u>	Wheel Well Clearance (Front)	<u>6.00</u>	Bottom Frame Height - Front	<u>12.50</u>				
Wheel Center Height Rear	<u>14.75</u>	Wheel Well Clearance (Rear)	<u>9.25</u>	Bottom Frame Height - Rear	<u>22.50</u>				

RANGE LIMIT: A=78 ±2 inches; C=237 ±13 inches; E=148 ±12 inches; F=39 ±3 inches; G = > 28 inches; H = 63 ±4 inches; O=43 ±4 inches; (M+N)/2=67 ±1.5 inches

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front <u>3700</u>	M_{front} _____	<u>2877</u>	<u>2832</u>	<u>2832</u>
Back <u>3900</u>	M_{rear} _____	<u>2013</u>	<u>2206</u>	<u>2206</u>
Total <u>6700</u>	M_{Total} _____	<u>4890</u>	<u>5038</u>	<u>5038</u>

(Allowable Range for TIM and GSM = 5000 lb ±110 lb)

Mass Distribution:

lb LF: 1393 RF: 1439 LR: 1157 RR: 1049




Table F.2. Measurements of Vehicle Vertical CG for Test No. 608331-01-6.

Date: 2019-12-19 Test No.: 608331-6 VIN: 1C6RR6FT8DS724487
 Year: 2013 Make: RAM Model: 1500
 Body Style: Quad Cab Mileage: 144145
 Engine: 4.7 liter V-8 Transmission: Automatic
 Fuel Level: Empty Ballast: 180 (440 lb max)
 Tire Pressure: Front: 35 psi Rear: 35 psi Size: 265/70 R 17

Measured Vehicle Weights: (lb)							
LF:	1393		RF:	1439		Front Axle:	2832
LR:	1157		RR:	1049		Rear Axle:	2206
Left:	2550		Right:	2488		Total:	5038
							5000 ±110 lb allowed
Wheel Base:	140.50	inches	Track: F:	68.50	inches	R:	68.00 inches
148 ±12 inches allowed			Track = (F+R)/2 = 67 ±1.5 inches allowed				
Center of Gravity, SAE J874 Suspension Method							
X:	61.52	inches	Rear of Front Axle	(63 ±4 inches allowed)			
Y:	-0.42	inches	Left -	Right +	of Vehicle Centerline		
Z:	29.00	inches	Above Ground	(minimum 28.0 inches allowed)			

Hood Height: 46.00 inches Front Bumper Height: 27.00 inches
 43 ±4 inches allowed

Front Overhang: 40.00 inches Rear Bumper Height: 30.00 inches
 39 ±3 inches allowed

Overall Length: 227.50 inches
 237 ±13 inches allowed

Table F.3. Exterior Crush Measurements for Test No. 608331-01-6.

Date: 2019-12-19 Test No.: 608331-6 VIN No.: 1C6RR6FT8DS724487
 Year: 2013 Make: RAM Model: 1500

VEHICLE CRUSH MEASUREMENT SHEET¹

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____ Corner shift: A1 _____ A2 _____ End shift at frame (CDC) (check one) < 4 inches _____ ≥ 4 inches _____	Bowing: B1 _____ X1 _____ B2 _____ X2 _____ Bowing constant $\frac{X1 + X2}{2} = \underline{\hspace{2cm}}$

Note: Measure C₁ to C₆ from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L ^{***}	C ₁	C ₂	C ₃	C ₄	C ₅	C ₆	±D
		Width ^{**} (CDC)	Max ^{****} Crush								
1	Front plane at bmpr ht	18	16	-	16	-	-	-	-	-	-
2	Side plane at bmpr ht	18	20	54	2	4	9	12	18	20	+70
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

¹Table taken from National Accident Sampling System (NASS).

*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




**Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

***Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

Table F.4. Occupant Compartment Measurements for Test No. 608331-01-6.

Date: 2019-12-19 Test No.: 608331-6 VIN No.: 1C6RR6FT8DS724487
 Year: 2013 Make: RAM Model: 1500



OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT

	Before	After (inches)	Differ.
A1	65.00	65.00	0.00
A2	63.00	63.00	0.00
A3	65.50	65.50	0.00
B1	45.00	45.00	0.00
B2	38.00	38.00	0.00
B3	45.00	45.00	0.00
B4	39.50	39.50	0.00
B5	43.00	43.00	0.00
B6	39.50	39.50	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	26.00	0.00
D1	11.00	11.00	0.00
D2	0.00	0.00	0.00
D3	11.50	11.50	0.00
E1	58.50	58.50	0.00
E2	63.50	63.50	0.00
E3	63.50	63.50	0.00
E4	63.50	63.50	0.00
F	59.00	59.00	0.00
G	59.00	59.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	25.00	25.00	0.00

*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.

F2 SEQUENTIAL PHOTOGRAPHS



0.000 s



0.100 s



0.200 s



0.300 s



Figure F.1. Sequential Photographs for Test No. 608331-01-6 (Overhead and Frontal Views).



0.400 s



0.500 s



0.600 s



0.700 s



Figure F.1. Sequential Photographs for Test No. 608331-01-6 (Overhead and Frontal Views) (Continued).



0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s




0.300 s



0.700 s

Figure F.2. Sequential Photographs for Test No. 608331-01-6 (Rear View).


Roll, Pitch, and Yaw Angles



— Roll — Pitch — Yaw

Axes are vehicle-fixed.
Sequence for determining orientation:

1. Yaw.
2. Pitch.
3. Roll.




Test Number: 608331-01-6
 Test Standard Test Number: MASH Test 3-21
 Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Test Vehicle: 2013 RAM 1500 Pickup
 Inertial Mass: 5038 lb
 Gross Mass: 5038 lb
 Impact Speed: 62.6 mi/h
 Impact Angle: 24.9°

Figure F.3. Vehicle Angular Displacements for Test No. 608331-01-6.

X Acceleration at CG

F4 VEHICLE ACCELERATIONS




— Time of OIV (0.1439 sec) — SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-6
Test Standard Test Number: MASH Test 3-21
Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
Test Vehicle: 2013 RAM 1500 Pickup
Inertial Mass: 5038 lb
Gross Mass: 5038 lb
Impact Speed: 62.6 mi/h
Impact Angle: 24.9°

Figure F.4. Vehicle Longitudinal Accelerometer Trace for Test No. 608331-01-6 (Accelerometer Located at Center of Gravity).

Y Acceleration at CG




— Time of OIV (0.1439 sec) — SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-6
 Test Standard Test Number: MASH Test 3-21
 Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
 Test Vehicle: 2013 RAM 1500 Pickup
 Inertial Mass: 5038 lb
 Gross Mass: 5038 lb
 Impact Speed: 62.6 mi/h
 Impact Angle: 24.9°

Figure F.5. Vehicle Lateral Accelerometer Trace for Test No. 608331-01-6 (Accelerometer Located at Center of Gravity).

Z Acceleration at CG



— SAE Class 60 Filter — 50-msec average

Test Number: 608331-01-6
Test Standard Test Number: MASH Test 3-21
Test Article: 2019 MASH 2-Tube Bridge Rail Thrie Beam Transition
Test Vehicle: 2013 RAM 1500 Pickup
Inertial Mass: 5038 lb
Gross Mass: 5038 lb
Impact Speed: 62.6 mi/h
Impact Angle: 24.9°

**Figure F.6. Vehicle Vertical Accelerometer Trace for Test No. 608331-01-6
(Accelerometer Located at Center of Gravity).**